



SPECIAL SHAPES

Denton | Elgin | Perla
Tulsa | Montgomery



Table of Contents

Introduction, Selection & Profiles	3
Ordering	4
Planning & Production Notes	5
Brick Sizes, Textures & Info	6
Brick Terms	8

Shapes

Flat Watertables (2 ¼" height)	12
Rowlock Watertables (3 ⅝" height)	34
Window Sills	56
Rowlock Wall Caps	78
Soldiers	100
Copings	120
Treads	122
Wall Examples	124
Corners	126
Shelf Angles & Radials	134
Solids	142
Arches	146
Reading Shape Documentation	174



I'm Interactive!

This pdf file allows you to click various buttons to navigate between the gallery page for each section, the shapes themselves, and this table of contents.

Introduction

Innovative uses of brick in load-bearing brick structures and conventional brick construction has resulted in brick buildings which are often exciting expressions in architectural design. Brick shapes allow architects to design buildings with interesting angles and forms. Dramatic depth and shadows in openings can be attained by using brick shapes at corners and in deep reveals at soffits, lintels, and sills.

Acme Brick's objective is to manufacture brick shapes which will assist architects in designing more functional and aesthetically pleasing buildings at the most economical cost.

We offer a wide variety of colors and textures in special shape brick by manufacturing shapes at five brick plants:

- Denton, Texas
- Elgin, Texas
- Perla in Malvern, Arkansas
- Montgomery, Alabama
- and Tulsa, Oklahoma.

Selection

All shapes illustrated in this brochure are shown for common sizes, with dimensions in a chart. The drawings are marked with **FF** for the exposed finished face. Special brick shapes shown are typical, and variations of shapes for a particular use can often be manufactured. *Each of the plants that create special shapes has its own unique skill set and method; accordingly, not every shape can be made at every plant.*

The color and texture of special shape brick is intended to be as close as possible to that of the standard field brick, but is subject to limitations of manufacturing. Some brick shapes cannot be stacked for firing in the kiln in the same direction as the field brick. This can cause a variation in kiln atmosphere at high temperatures which may produce a slight color difference.

Shapes made by hand may show a slight texture difference than a field brick made mechanically. If textures are desired to be in a certain direction on a particular face of a shape, it will need to be noted on the Approval Drawings, otherwise it will be to the discretion of the plant to best manufacture the shape.

Profiles

- 

01 Sloped
- 

02 Bullnose
- 

03 Cove
- 

04 Ogee
- 

05 Bullnose Ogee
- 

06 Cove Ogee
- 

07 Crown Ogee
- 

08 Bullnose Flat
- 

09 Full Bullnose
- 

10 Coping

These are the most common profiles.

For quick reference we have created icons.

Look for them throughout the book.

** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Ordering

Special shape brick are considered a custom made item. They are manufactured to order for a specific project. Manufacturing cannot begin until an order has been placed for firm quantities, and shape drawings have been approved. To eliminate errors and to facilitate estimating quantities, Acme Brick will provide drawings of each shape showing the plan, elevations, and dimensions for each shape. All exposed brick faces will be clearly identified, and the coring of the unit will be shown. Brick coursing will be indicated in the areas where shapes are used. Upon completion the architect will receive these drawings for final inspection and approval. See pages 178-180 for more information.

Pricing may vary considerably from plant to plant and from blend to blend; quantities may also affect pricing. Be aware that the difficulty in manufacturing sanded or heritage textures on special shapes will incur extra cost.


Your Acme Brick sales representative is qualified to help you with planning shapes for your next project. It is important to speak with your representative to ensure that your chosen plant can accommodate your order.

For more details check out our Pocket Guide to Brick Construction

Available online here:



Planning



Packing



Installation


Completion



Planning Notes

Acme Brick provides drawings of each shape showing the plan, elevations, and dimensions; however, it is important for the architect to fully flesh out the individual project and uses for these shapes. As these are “special” shapes, it is important to understand their placement within a wall structure to ensure the desired look on the outside.

For example, a watertable shape, as shown here, can create an attractive division in a wall. The inclusion of the special shape means that the brick above will be stepped back to continue the face plane. This requires the architect to plan for that space behind the wall face.



Brick Textures

If textures are desired to be in a certain direction on a particular face of a shape, please note it on the approval drawings, otherwise it will be up to the discretion of the plant to best manufacture the shape.



Smooth



Velour
(aka wirecut)



Blade Cut



Craftwork
(aka ironspot)



Rustic



Heritage



Ruff



Bark



Vertical

** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.


Brick Sizes

	Thickness	Height	Length
Modular (MOD)	3 5⁄8"	2 1⁄4"	7 5⁄8"
Norman (NOR)	3 5⁄8"	2 1⁄4"	11 5⁄8"
Queen (QSZ)	2 3⁄4"	2 3⁄4"	7 5⁄8"
King (KSZ)	2 3⁄4"	2 5⁄8"	9 5⁄8"
Estate (EST)	2 3⁄4"	3 5⁄8"	9 5⁄8"
Closure (CLS) (aka Engineer Modular)	3 5⁄8"	3 5⁄8"	7 5⁄8"
Utility (UTL)	3 5⁄8"	3 5⁄8"	11 5⁄8"


Shape Nomenclature: [Shape Type]-[Profile]-[Piece]
(eg. FWT-01-1 = Flat Water Table - Sloped - Header)

When ordering include the three letter size codes:
MOD - Modular, NOR - Norman, QSZ - Queen, KSZ - King,
EST - Estate, CLS - Closure, UTL - Utility


Colors and sizes vary at each plant. Not all shapes can be made at every location.
Be sure to check with your sales representative before making selections.




Modular




Norman




Queen




King



Estate




Closure




Utility


Brick Position Nomenclature




Stretcher




Header




Rowlock




Soldier




Shiner




Sailor



Single Wythe




Double Wythe




Course


Traditional Bond Patterns




Running Bond




1⁄3 Running Bond




Common Bond
6th Course Header




English Bond




Stack Bond



Flemish Bond



Common Bond
6th Course
Flemish Header



English Cross
or Dutch Bond

Brick Terms

Angle Brick - Any brick or masonry unit shaped to an oblique angle to fit a salient corner.

Arch - A vertically curved compressive structural member spanning openings or recesses.

Arch Brick - Wedge-shaped brick for special use in an arch. Also refers to the hard burned brick units found in the arch section of a scove kiln.

Band Course - A continuous, horizontal band of masonry marking a division in the wall elevation. Sometimes called belt course, string course, or sill course.

Bevel - An inclined surface of a solid object which connects two orthogonal sides.

Bond - (1) The arrangement of units to provide strength, stability, and pattern. (2) Adhesion between mortar or grout and masonry units or reinforcement. (3) To connect wythes or units. (4) Tying various parts of a masonry wall by lapping units one over another or with metal ties or reinforcing.

Brick - A solid or hollow manufactured masonry unit, usually formed into a small rectangular prism.

Buttress - A projecting mass of masonry set at an angle to or bonded into a wall that it strengthens or supports. A buttress decreases in its cross-sectional area from top to base.

Cantilever - A structural member, supported at only one end, that projects from its support.

Capstone - Any single stone at the top of a masonry structure.

Ceramic - A broad term for products made from heat-resistant, non-metallic, inorganic materials such as clay, bauxite, alumina, silica magnesia, silicone carbide, and the like which have been fired to incipient fusion.

Chamfer - To bevel an arris or edge.

Chimney - A shaft built to carry off smoke.

Clay - A natural mineral consisting essentially of hydrous aluminum silicate. It is plastic when moistened, stiff when dried, and vitrified when fired beyond maturing temperature.

Clay Brick - A ceramic brick of clay or shale, formed while plastic and fired in a kiln.

Closer - (1) The last masonry or portion of a unit laid in a course. (2) A stone course running from one window sill to another (a variety of string course).

Closure Unit - Supplementary or shorter length units used at corners or jambs to maintain bond patterns.

Column - A relatively long, slender structural compression member supporting loads along its axis.

Common Brick - Brick for building purposes not especially treated for texture or color.

Corbel - (1) The projection of successive courses of masonry out from the face of the wall to increase the wall thickness or to form a shelf or ledge. (2) A shelf or ledge formed by successive courses of masonry projecting out from the face of a wall, pier, or column.

Core - A hollow space within a concrete masonry unit formed by the face shells and webs. The holes in clay units.

Cornice - The molding or series of moldings forming the top member of a facade, door or window frame, or interior wall.

Course - A layer (range) of masonry units running horizontally in a wall or, much less commonly, curved over an arch.

Durability - The ability of a material to resist weathering action, chemical attack, abrasion, and other conditions of service.

Edgeset - A brick set on its narrow side instead of on its flat side, especially during drying and firing.

Brick Terms (continued)

Empirical Design - A design based on the application of physical limitations learned from experience or observations gained through experience, without a structural analysis

Face - The exposed surface of a wall or masonry unit.

Facing - Any material, forming a part of a wall, used as a finished surface.

Facing Brick - Brick made especially for facing, or exposure purposes, and often treated to produce special surface textures. These bricks are made of selected clays, or treated, to produce the desired color.

Fascia - A flat horizontal band that appears as a vertical face. The fascia is used decoratively, alone or in combination with moldings.

Fire Brick - Brick made of refractory ceramic material that will resist high temperatures.

Fire Clay - A clay that is highly resistant to heat without deforming and used for making brick.

Foundation Wall - Walls below the floor nearest grade serving as a support for a wall, pier, column, or other structural part of a building.

Freeze-Thaw - Freezing and thawing of moisture in materials and the resultant effects on these materials and on structures of which they are a part or with which they are in contact.

Frog - A depression in the bed surface of a brick, sometimes called a panel.

Gauged Brick - (1) Brick that has been ground or otherwise produced with accurate dimensions. (2) A tapered arch brick.

Hacking - (1) The procedure of stacking brick in a kiln or on a kiln car. (2) Laying brick with the bottom edge set in from the plane surface of the wall.

Header - A masonry unit that overlaps two or more adjacent wythes of masonry to tie them together. Also called a bonder.

Header Course - A continuous bonding course of header brick. Also called a heading course.

Jack Arch - An arch that has little or no curvature.

Jumbo Brick - A generic term indicating a brick larger in size than the standard. Some producers use this term to describe oversize brick of specific dimensions manufactured by them.

Kerf - A cut or removal of material in a unit to facilitate breaking the unit to a desired shape or length.

Kiln - A furnace, oven, or heated enclosure used for burning or firing brick or other clay material.

Lap - The distance one masonry unit extends over another.

Major Arch - Arch with span greater than six feet.

Masonry - (1) Strictly speaking, the art of building in stone. By extension, masonry has come to mean the practice of the mason's craft with brick, tile, concrete masonry units and other materials. (2) The work resulting from the practice of the mason's craft - structures built of stone, brick, or other materials set as units in patterns and amenable to assembly with mortar, whether or not mortar is actually used. (3) The type of construction made up of masonry units laid up with mortar or grout or other accepted method of jointing. (4) An assemblage of masonry units.

Masonry Opening - The space left open in a wall between masonry units, for example the space of an arch or window.

Masonry Unit - Natural or manufactured building units of burned clay, concrete, stone, glass, gypsum, etc.

Masonry Veneer - A non-loadbearing facing of masonry attached to its structural backing but not relied upon to strengthen the wall.

Minor Arch - Arch with a span of less than six feet.

Brick Terms (continued)

Modular Coordination - A dimensional system affording more efficient assembly of buildings from standard building products by correlating the dimensions of a structure and the unit sizes of the materials going into it, through reference to a four inch cubical module. Efficient use eliminates extra work hours and waste of materials.

Modular Design - Constructed with standardized units or dimensions for flexibility and variety in use.

Parapet - A low wall around the perimeter of a building at roof level or around balconies.

Partition - An interior wall one story or less in height. It is generally non-loadbearing.

Pier - An isolated column of masonry, not bonded to associated masonry.

Pierced Wall - A masonry wall in which an ornamental pierced effect is achieved by alternating rectangular or shaped blocks with open spaces.

Prefabricated Masonry - Masonry fabricated in a location other than its final location in the structure. Also known as pre-assembled, panelized, and sectionalized masonry.

Prism - Any solid shape with only vertical and horizontal faces.

Quoin - (1) One of a series of masonry corner blocks, differing in size, finish, or material from the adjacent walling. (2) A wedge-shaped piece of stone. May be used in either the corner treatment described above (although most quoin stones are not wedge-shaped) or as a chock, a shim, or a device for leveling or aligning.

Racking - Stepping back successive courses of masonry.

Reinforced Masonry - (1) Masonry containing reinforcement in the grouted joints or grouted cores to resist shearing and tensile stresses. (2) Unit masonry in which reinforcement is embedded in such a manner that the component materials act together in resisting shearing and tensile forces.

Relieving Arch - An arch, usually blind, built into the wall above a lintel or flat arch to carry the load to walls or other supporting members.

Roman Arch - A semicircular arch. If built of stone, all units are wedge-shaped.

Rowlock - A brick laid on its face edge with the end surface visible in the wall face. Frequently spelled rolok. Always 3 5/8" high.

Sewer Brick - Low absorption, abrasive-resistant brick intended for use in drainage structures.

Sill - A flat or slightly beveled stone set horizontally at the base of an opening in a wall.

Soffit - The exposed lower surface of any overhead component of a building such as a lintel, vault, or cornice, or an arch or entablature.

Solid - A standard brick size without cores.

Soldier - A brick set on end with its face showing on the wall surface.

Stack - Any structure or part thereof that contains a flue or flues for the discharge of gases. Also called a chimney.

Standard - An accepted measure of comparison for a quantitative or qualitative value.

Stretcher - A masonry unit laid with its greatest dimension horizontal and its face parallel to the wall face.

Texture - The pattern or configuration apparent in an exposed surface, as in concrete and mortar, including roughness, streaking, striation, or departure from flatness.

Trimmer Arch - An arch, usually a low-rise arch of brick, used for supporting a fireplace hearth.

Veneer - A single facing wythe of masonry units or similar materials securely attached to a wall for the purpose of providing ornamentation, protection, insulation, etc., but not adding strength to the wall.

Wall - A vertical planar member of a structure, enclosing or dividing space.

Brick Terms (continued)

Wall, Prestressed - Reinforced concrete or masonry walls in which internal stresses have been introduced to reduce potential tensile stresses in the wall resulting from imposed loads.

Wall, Reinforced - A masonry wall reinforced with embedded steel so that the two materials act together in resisting forces on the wall.

Wall, Retaining - A wall designed to prevent the movement of soils and structures placed on one side of it.

Wall, Screen - A masonry solar shading wall usually made of decorative bricks or tile.

Wall, Serpentine - A single-wythe wall built with curves in plan to strengthen it.

Wall, Shear - A wall which carries shear loads in its own plane.

Wall, Single Wythe - A wall of only one masonry unit in thickness.

Wall, Spandrel - That portion of a panel or curtain wall above the head of a window or door in one story and below the sill of the window in the story above.

Water Table - A projection of lower masonry on the outside of the wall slightly above the ground. Often a damp course is placed at the level of the water table to prevent upward penetration of ground water. Generally near grade and having a beveled top and a drip cut in the projecting underside to deflect water. Always 2 1/4" high.

Workmanship - The art or skill of a workman. Craftsmanship. Quality imparted to a masonry wall or floor in the process of building it.

Wythe - Each continuous vertical section of a wall, one masonry unit in thickness, and tied to its adjacent vertical section or sections by bonders, metal ties, or grout.



Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Flat Watertables









































SLOPED				
	FWT-01-1 Flat Watertable - Sloped - Header	FWT-01-2 Flat Watertable - Sloped - Outside Corner	FWT-01-3 Flat Watertable - Sloped - Inside Corner	FWT-01-4 Flat Watertable - Sloped - Stretcher
				
	FWT-02-1 Flat Watertable - Bullnose - Header	FWT-02-2 Flat Watertable - Bullnose - Outside Corner	FWT-02-3 Flat Watertable - Bullnose - Inside Corner	FWT-02-4 Flat Watertable - Bullnose - Stretcher
COVE				
	FWT-03-1 Flat Watertable - Cove - Header	FWT-03-2 Flat Watertable - Cove - Outside Corner	FWT-03-3 Flat Watertable - Cove - Inside Corner	FWT-03-4 Flat Watertable - Cove - Stretcher
				
	FWT-04-1 Flat Watertable - Ogee - Header	FWT-04-2 Flat Watertable - Ogee - Outside Corner	FWT-04-3 Flat Watertable - Ogee - Inside Corner	FWT-04-4 Flat Watertable - Ogee - Stretcher
BULLNOSE OGEE				
	FWT-05-1 Flat Watertable - Bullnose Ogee - Header	FWT-05-2 Flat Watertable - Bullnose Ogee - Outside Corner	FWT-05-3 Flat Watertable - Bullnose Ogee - Inside Corner	FWT-05-4 Flat Watertable - Bullnose Ogee - Stretcher

Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Flat Watertables (Continued)

COVE OGEE				
	FWT-06-1 Flat Watertable - Cove Ogee - Header	FWT-06-2 Flat Watertable - Cove Ogee - Outside Corner	FWT-06-3 Flat Watertable - Cove Ogee - Inside Corner	FWT-06-4 Flat Watertable - Cove Ogee - Stretcher
				
	FWT-07-1 Flat Watertable - Crown Ogee - Header	FWT-07-2 Flat Watertable - Crown Ogee - Outside Corner	FWT-07-3 Flat Watertable - Crown Ogee - Inside Corner	FWT-07-4 Flat Watertable - Crown Ogee - Stretcher
BULLNOSE FLAT				
	FWT-08-1 Flat Watertable - Bullnose Flat - Header	FWT-08-2 Flat Watertable - Bullnose Flat - Outside Corner	FWT-08-3 Flat Watertable - Bullnose Flat - Inside Corner	FWT-08-4 Flat Watertable - Bullnose Flat - Stretcher
				
	FWT-09-1 Flat Watertable - Full Bullnose - Header	FWT-09-2 Flat Watertable - Full Bullnose - Outside Corner	FWT-09-3 Flat Watertable - Full Bullnose - Inside Corner	FWT-09-4 Flat Watertable - Full Bullnose - Stretcher
COPING				
	FWT-10-1 Flat Watertable - Coping - Header	FWT-10-2 Flat Watertable - Coping - Outside Corner	FWT-10-3 Flat Watertable - Coping - Inside Corner	FWT-10-4 Flat Watertable - Coping - Stretcher

** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.




Flat Watertable - Sloped

Table of Contents


Watertable Gallery

FWT-01-1 Header




FWT-01-1	FLAT WATERTABLE - SLOPED - HEADER				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 1/8"	3/4"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 1/8"	3/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 1/8"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	8 1/8"	1 1/8"
ESTATE	3 5/8"	9 5/8"	2 5/8"	8 1/8"	2 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	2 1/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	2 1/8"

FWT-01-2 Outside Corner




FWT-01-2	FLAT WATERTABLE - SLOPED - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 1/8"	1 1/8"
KING	2 5/8"	2 5/8"	2 5/8"	1 1/8"	1 1/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"

FWT-01-3 Inside Corner



FWT-01-3	FLAT WATERTABLE - SLOPED - INSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 1/8"	1 1/8"
KING	2 5/8"	2 5/8"	2 5/8"	1 1/8"	1 1/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"

FWT-01-4 Stretcher



FWT-01-4	FLAT WATERTABLE - SLOPED - STRETCHER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 1/8"	3/4"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 1/8"	3/4"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2 1/8"	1 1/8"
KING	2 5/8"	3 5/8"	9 5/8"	2 1/8"	1 1/8"
ESTATE	3 5/8"	3 5/8"	9 5/8"	2 1/8"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	2 1/8"	2 1/8"
UTILITY	3 5/8"	3 5/8"	11 5/8"	2 1/8"	2 1/8"




Flat Watertable - Sloped

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Bullnose

Table of Contents


Watertable Gallery

FWT-02-1 Header




FWT-02-1	FLAT WATERTABLE - BULLNOSE - HEADER				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	5 5/8"	2"
NORMAN	2 1/4"	11 5/8"	3 5/8"	9 5/8"	2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 1/4"	2 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 1/4"	2 3/8"
ESTATE	3 5/8"	9 5/8"	2 5/8"	6 13/32"	3 7/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 13/32"	3 7/32"

FWT-02-2 Outside Corner




FWT-02-2	FLAT WATERTABLE - BULLNOSE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 5/8"	2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 5/8"	2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1/4"	2 3/8"
KING	2 5/8"	2 5/8"	2 5/8"	1/4"	2 3/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"

FWT-02-3 Inside Corner



FWT-02-3	FLAT WATERTABLE - BULLNOSE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 5/8"	2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 5/8"	2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1/4"	2 3/8"
KING	2 5/8"	2 5/8"	2 5/8"	1/4"	2 3/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"

FWT-02-4 Stretcher



FWT-02-4	FLAT WATERTABLE - BULLNOSE - STRETCHER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	7 5/8"	1 5/8"	2"
NORMAN	2 1/4"	3 5/8"	11 5/8"	1 5/8"	2"
QUEEN	2 5/8"	3 5/8"	7 5/8"	1 1/4"	2 3/8"
KING	2 5/8"	3 5/8"	9 5/8"	1 1/4"	2 3/8"
ESTATE	3 5/8"	3 5/8"	9 5/8"	13/32"	3 7/32"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	13/32"	3 7/32"
UTILITY	3 5/8"	3 5/8"	11 5/8"	13/32"	3 7/32"




Flat Watertables - Bullnose

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Cove


- Table of Contents
- Watertable Gallery

FWT-03-1 Header




FWT-03-1	FLAT WATERTABLE - COVE - HEADER					
	A	B	C	D	E	F
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 1/8"	3/4"	1 1/2"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 1/8"	3/4"	2 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"
ESTATE	3 5/8"	9 5/8"	2 5/8"	7 7/32"	1 7/32"	2 13/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"

FWT-03-2 Outside Corner




FWT-03-2	FLAT WATERTABLE - COVE - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"	1 1/2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"	1 1/2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	7/8"	7/8"	1 3/4"
KING	2 5/8"	2 5/8"	2 5/8"	7/8"	7/8"	1 3/4"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"

FWT-03-3 Inside Corner



FWT-03-3	FLAT WATERTABLE - COVE - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"	1 1/2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/8"	3/4"	1 1/2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	7/8"	7/8"	1 3/4"
KING	2 5/8"	2 5/8"	2 5/8"	7/8"	7/8"	1 3/4"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"

FWT-03-4 Stretcher




FWT-03-4	FLAT WATERTABLE - COVE - STRETCHER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 1/8"	3/4"	1 1/2"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 1/8"	3/4"	1 1/2"
QUEEN	2 5/8"	3 5/8"	7 5/8"	1 7/8"	7/8"	1 3/4"
KING	2 5/8"	3 5/8"	9 5/8"	1 7/8"	7/8"	1 3/4"
ESTATE	3 5/8"	3 5/8"	9 5/8"	1 7/32"	1 7/32"	2 13/32"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	1 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	3 5/8"	11 5/8"	1 7/32"	1 7/32"	2 13/32"



Flat Watertables - Cove

- Table of Contents
- Watertable Gallery

Wall Diagram






Flat Watertables - Ogee

Table of Contents


Watertable Gallery

FWT-04-1 Header




FWT-04-1	FLAT WATERTABLE - OGEE - HEADER				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 7/32"	1 1/4"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 7/32"	1 1/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6"	1 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	8"	1 7/16"
ESTATE	3 5/8"	9 5/8"	2 5/8"	7 3/8"	2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 3/8"	2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 3/8"	2"

FWT-04-2 Outside Corner




FWT-04-2	FLAT WATERTABLE - OGEE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 7/32"	1 1/4"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 7/32"	1 1/4"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1"	1 7/16"
KING	2 5/8"	2 5/8"	2 5/8"	1"	1 7/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"

FWT-04-3 Inside Corner



FWT-04-3	FLAT WATERTABLE - OGEE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 7/32"	1 1/4"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 7/32"	1 1/4"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1"	1 7/16"
KING	2 5/8"	2 5/8"	2 5/8"	1"	1 7/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"

FWT-04-4 Stretcher



FWT-04-4	FLAT WATERTABLE - OGEE - STRETCHER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 7/32"	1 1/4"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 7/32"	1 1/4"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2"	1 7/16"
KING	2 5/8"	3 5/8"	9 5/8"	2"	1 7/16"
ESTATE	3 5/8"	3 5/8"	9 5/8"	1 3/8"	2"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	1 3/8"	2"
UTILITY	3 5/8"	3 5/8"	11 5/8"	1 3/8"	2"




Flat Watertables - Ogee

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Bullnose Ogee

Table of Contents


Watertable Gallery

FWT-05-1 Header




FWT-05-1	FLAT WATERTABLE - BULLNOSE OGEE - HEADER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 15/16"	11/16"	1 7/8"	7 1/32"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 15/16"	11/16"	1 7/8"	11 1/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 13/16"	13/16"	2 3/16"	6 15/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 13/16"	13/16"	2 3/16"	8 15/16"
ESTATE	3 5/8"	9 5/8"	2 5/8"	8 1/2"	1 1/8"	3"	8 21/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/2"	1 1/8"	3"	6 21/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/2"	1 1/8"	3"	10 21/32"

FWT-05-2 Outside Corner




FWT-05-2	FLAT WATERTABLE - BULLNOSE OGEE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 13/16"	13/16"	2 3/16"	1 15/16"
KING	2 5/8"	2 5/8"	2 5/8"	1 13/16"	13/16"	2 3/16"	1 15/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"

FWT-05-3 Inside Corner



FWT-05-3	FLAT WATERTABLE - BULLNOSE OGEE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 13/16"	13/16"	2 3/16"	1 15/16"
KING	2 5/8"	2 5/8"	2 5/8"	1 13/16"	13/16"	2 3/16"	1 15/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"

FWT-05-4 Stretcher



FWT-05-4	FLAT WATERTABLE - BULLNOSE OGEE - STRETCHER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 15/16"	11/16"	1 7/8"	3 1/32"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
KING	2 5/8"	3 5/8"	9 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
ESTATE	3 5/8"	3 5/8"	9 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
UTILITY	3 5/8"	3 5/8"	11 5/8"	2 1/2"	1 1/8"	3"	2 21/32"




Flat Watertables - Bullnose Ogee

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Cove Ogee

Table of Contents


Watertable Gallery

FWT-06-1 Header




FWT-06-1	FLAT WATERTABLE - COVE OGEE - HEADER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	7 5/8"	3 5/8"	5 27/32"	15/32"	13/16"	31/32"
NORMAN	2 1/4"	11 5/8"	3 5/8"	9 27/32"	15/32"	13/16"	31/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 9/16"	9/16"	15/16"	1 1/8"
ESTATE	3 5/8"	9 5/8"	2 5/8"	6 3/4"	3/4"	1 5/16"	1 9/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 3/4"	3/4"	1 5/16"	1 9/16"

FWT-06-2 Outside Corner




FWT-06-2	FLAT WATERTABLE - COVE OGEE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 27/32"	15/32"	13/16"	31/32"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 27/32"	15/32"	13/16"	31/32"
QUEEN	2 5/8"	2 5/8"	2 5/8"	9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	2 5/8"	2 5/8"	9/16"	9/16"	15/16"	1 1/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"

FWT-06-3 Inside Corner



FWT-06-3	FLAT WATERTABLE - COVE OGEE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 27/32"	15/32"	13/16"	31/32"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 27/32"	15/32"	13/16"	31/32"
QUEEN	2 5/8"	2 5/8"	2 5/8"	9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	2 5/8"	2 5/8"	9/16"	9/16"	15/16"	1 1/8"
ESTATE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"

FWT-06-4 Stretcher



FWT-06-4	FLAT WATERTABLE - COVE OGEE - STRETCHER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	7 5/8"	1 27/32"	15/32"	13/16"	31/32"
NORMAN	2 1/4"	3 5/8"	11 5/8"	1 27/32"	15/32"	13/16"	31/32"
QUEEN	2 5/8"	3 5/8"	7 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	3 5/8"	9 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
ESTATE	3 5/8"	3 5/8"	9 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	3 5/8"	11 5/8"	3/4"	3/4"	1 5/16"	1 9/16"




Flat Watertables - Cove Ogee

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Crown Ogee

Table of Contents


Watertable Gallery

FWT-07-1 Header




FWT-07-1	FLAT WATERTABLE - CROWN OGEE - HEADER							
	A	B	C	D	E	F	G	H
MODULAR	2 1/4"	7 5/8"	3 5/8"	7 1/16"	11/32"	9/16"	1 3/16"	6"
NORMAN	2 1/4"	11 5/8"	3 5/8"	11 1/16"	11/32"	9/16"	1 3/16"	10"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 15/16"	13/32"	11/16"	1 3/8"	5 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"
ESTATE	3 5/8"	9 5/8"	2 5/8"	8 11/16"	9/16"	15/16"	1 29/32"	7 1/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"

FWT-07-2 Outside Corner




FWT-07-2	FLAT WATERTABLE - CROWN OGEE - OUTSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	2 1/4"	3 5/8"	3 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 15/16"	13/32"	11/16"	1 3/8"	3/4"
KING	2 5/8"	2 5/8"	2 5/8"	1 15/16"	13/32"	11/16"	1 3/8"	3/4"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"

FWT-07-3 Inside Corner



FWT-07-3	FLAT WATERTABLE - CROWN OGEE - INSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	2 1/4"	3 5/8"	3 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
NORMAN	2 1/4"	3 5/8"	3 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 15/16"	13/32"	11/16"	1 3/8"	3/4"
KING	2 5/8"	2 5/8"	2 5/8"	1 15/16"	13/32"	11/16"	1 3/8"	3/4"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"

FWT-07-4 Stretcher



FWT-07-4	FLAT WATERTABLE - CROWN OGEE - STRETCHER							
	A	B	C	D	E	F	G	H
MODULAR	2 1/4"	3 5/8"	7 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
NORMAN	2 1/4"	3 5/8"	11 5/8"	3 1/16"	11/32"	9/16"	1 3/16"	2"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2 15/16"	13/32"	11/16"	1 3/8"	1 3/4"
KING	2 5/8"	3 5/8"	9 5/8"	2 15/16"	13/32"	11/16"	1 3/8"	1 3/4"
ESTATE	3 5/8"	3 5/8"	9 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"
UTILITY	3 5/8"	3 5/8"	11 5/8"	2 11/16"	9/16"	15/16"	1 29/32"	1 1/32"




Flat Watertables - Crown Ogee

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Bullnose Flat

Table of Contents


Watertable Gallery

FWT-08-1 Header




FWT-08-1	FLAT WATERTABLE - BULLNOSE FLAT - HEADER					
	A	B	C	D	E	F
MODULAR	2 1/4"	7 5/8"	3 5/8"	5 3/4"	3/8"	1 7/8"
NORMAN	2 1/4"	11 5/8"	3 5/8"	9 3/4"	3/8"	1 7/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/16"	7/16"	2 3/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/16"	7/16"	2 3/16"
ESTATE	3 5/8"	9 5/8"	2 5/8"	6 5/8"	5/8"	3"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 5/8"	5/8"	3"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 5/8"	5/8"	3"

FWT-08-2 Outside Corner




FWT-08-2	FLAT WATERTABLE - BULLNOSE FLAT - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 3/4"	3/8"	1 7/8"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 3/4"	3/8"	1 7/8"
QUEEN	2 5/8"	2 5/8"	2 5/8"	7/16"	7/16"	2 3/16"
KING	2 5/8"	2 5/8"	2 5/8"	7/16"	7/16"	2 3/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
UTILITY	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"

FWT-08-3 Inside Corner



FWT-08-3	FLAT WATERTABLE - BULLNOSE FLAT - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	3 5/8"	1 3/4"	3/8"	1 7/8"
NORMAN	2 1/4"	3 5/8"	3 5/8"	1 3/4"	3/8"	1 7/8"
QUEEN	2 5/8"	2 5/8"	2 5/8"	7/16"	7/16"	2 3/16"
KING	2 5/8"	2 5/8"	2 5/8"	7/16"	7/16"	2 3/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
UTILITY	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"

FWT-08-4 Stretcher



FWT-08-4	FLAT WATERTABLE - BULLNOSE FLAT - STRETCHER					
	A	B	C	D	E	F
MODULAR	2 1/4"	3 5/8"	7 5/8"	1 3/4"	3/8"	1 7/8"
NORMAN	2 1/4"	3 5/8"	11 5/8"	1 3/4"	3/8"	1 7/8"
QUEEN	2 5/8"	3 5/8"	7 5/8"	1 7/16"	7/16"	2 3/16"
KING	2 5/8"	3 5/8"	9 5/8"	1 7/16"	7/16"	2 3/16"
ESTATE	3 5/8"	3 5/8"	9 5/8"	5/8"	5/8"	3"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	5/8"	5/8"	3"
UTILITY	3 5/8"	3 5/8"	11 5/8"	5/8"	5/8"	3"




Flat Watertables - Bullnose Flat

Table of Contents

Watertable Gallery

Wall Diagram






Flat Watertables - Full Bullnose


- Table of Contents
- Watertable Gallery

FWT-09-1 Header




FWT-09-1	FLAT WATERTABLE - FULL BULLNOSE - HEADER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 11/16"	3/8"	15/16"	6 11/16"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 11/16"	3/8"	15/16"	10 11/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 17/32"	7/16"	1 3/32"	6 17/32"
KING	2 5/8"	9 5/8"	2 5/8"	8 17/32"	7/16"	1 3/32"	8 17/32"
ESTATE	3 5/8"	9 5/8"	2 5/8"	8 1/8"	5/8"	1 1/2"	8 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	5/8"	1 1/2"	6 1/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	5/8"	1 1/2"	10 1/8"

FWT-09-2 Outside Corner




FWT-09-2	FLAT WATERTABLE - FULL BULLNOSE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 11/16"	3/8"	15/16"	2 11/16"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 11/16"	3/8"	15/16"	2 11/16"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 17/32"	7/16"	1 3/32"	1 17/32"
KING	2 5/8"	2 5/8"	2 5/8"	1 17/32"	7/16"	1 3/32"	1 17/32"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"

FWT-09-3 Inside Corner



FWT-09-3	FLAT WATERTABLE - FULL BULLNOSE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 11/16"	3/8"	15/16"	2 11/16"
NORMAN	2 5/8"	2 5/8"	2 5/8"	1 17/32"	7/16"	1 3/32"	1 17/32"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 17/32"	7/16"	1 3/32"	1 17/32"
KING	2 5/8"	2 5/8"	2 5/8"	1 17/32"	7/16"	1 3/32"	1 17/32"
ESTATE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"

FWT-09-4 Stretcher




FWT-09-4	FLAT WATERTABLE - FULL BULLNOSE - STRETCHER						
	A	B	C	D	E	F	G
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 11/16"	3/8"	15/16"	2 11/16"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 11/16"	3/8"	15/16"	2 11/16"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
KING	2 5/8"	3 5/8"	9 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
ESTATE	3 5/8"	3 5/8"	9 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
UTILITY	3 5/8"	3 5/8"	11 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"



Flat Watertables - Full Bullnose

- Table of Contents
- Watertable Gallery

Wall Diagram




Flat Watertables - Coping

Table of Contents


Watertable Gallery

FWT-10-1 Header




FWT-10-1	FLAT WATERTABLE - COPING - HEADER				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	6 1/2"	1 1/8"
NORMAN	2 1/4"	11 5/8"	3 5/8"	10 1/2"	1 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 5/16"	1 5/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 5/16"	1 5/16"
ESTATE	3 5/8"	9 5/8"	2 5/8"	7 13/16"	1 13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 13/16"	1 13/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 13/16"	1 13/16"

FWT-10-2 Outside Corner




FWT-10-2	FLAT WATERTABLE - COPING - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/2"	1 1/8"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/2"	1 1/8"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 5/16"	1 5/16"
KING	2 5/8"	2 5/8"	2 5/8"	1 5/16"	1 5/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"

FWT-10-3 Inside Corner



FWT-10-3	FLAT WATERTABLE - COPING - INSIDE CORNER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	3 5/8"	2 1/2"	1 1/8"
NORMAN	2 1/4"	3 5/8"	3 5/8"	2 1/2"	1 1/8"
QUEEN	2 5/8"	2 5/8"	2 5/8"	1 5/16"	1 5/16"
KING	2 5/8"	2 5/8"	2 5/8"	1 5/16"	1 5/16"
ESTATE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"

FWT-10-4 Stretcher



FWT-10-4	FLAT WATERTABLE - COPING - STRETCHER				
	A	B	C	D	E
MODULAR	2 1/4"	3 5/8"	7 5/8"	2 1/2"	1 1/8"
NORMAN	2 1/4"	3 5/8"	11 5/8"	2 1/2"	1 1/8"
QUEEN	2 5/8"	3 5/8"	7 5/8"	2 5/16"	1 5/16"
KING	2 5/8"	3 5/8"	9 5/8"	2 5/16"	1 5/16"
ESTATE	3 5/8"	3 5/8"	9 5/8"	1 13/16"	1 13/16"
CLOSURE	3 5/8"	3 5/8"	7 5/8"	1 13/16"	1 13/16"
UTILITY	3 5/8"	3 5/8"	11 5/8"	1 13/16"	1 13/16"

Flat Watertables - Coping

Table of Contents

Watertable Gallery

Wall Diagram




Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Rowlock Watertables































SLOPED			
	RWT-01-1 Rowlock Watertable - Sloped - Rowlock	RWT-01-2 Rowlock Watertable - Sloped - Outside Corner	RWT-01-3 Rowlock Watertable - Sloped - Inside Corner
BULLNOSE			
	RWT-02-1 Rowlock Watertable - Bullnose - Rowlock	RWT-02-2 Rowlock Watertable - Bullnose - Outside Corner	RWT-02-3 Rowlock Watertable - Bullnose - Inside Corner
COVE			
	RWT-03-1 Rowlock Watertable - Cove - Rowlock	RWT-03-2 Rowlock Watertable - Cove - Outside Corner	RWT-03-3 Rowlock Watertable - Cove - Inside Corner
OGEE			
	RWT-04-1 Rowlock Watertable - Ogee - Rowlock	RWT-04-2 Rowlock Watertable - Ogee - Outside Corner	RWT-04-3 Rowlock Watertable - Ogee - Inside Corner
BULLNOSE OGEE			
	RWT-05-1 Rowlock Watertable - Bullnose Ogee - Rowlock	RWT-05-2 Rowlock Watertable - Bullnose Ogee - Outside Corner	RWT-05-3 Rowlock Watertable - Bullnose Ogee - Inside Corner

Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Rowlock Watertables (Continued)

COVE OGEE			
	RWT-06-1 Rowlock Watertable - Cove Ogee - Rowlock	RWT-06-2 Rowlock Watertable - Cove Ogee - Outside Corner	RWT-06-3 Rowlock Watertable - Cove Ogee - Inside Corner
CROWN OGEE			
	RWT-07-1 Rowlock Watertable - Crown Ogee - Rowlock	RWT-07-2 Rowlock Watertable - Crown Ogee - Outside Corner	RWT-07-3 Rowlock Watertable - Crown Ogee - Inside Corner
BULLNOSE FLAT			
	RWT-08-1 Rowlock Watertable - Bullnose Flat - Rowlock	RWT-08-2 Rowlock Watertable - Bullnose Flat - Outside Corner	RWT-08-3 Rowlock Watertable - Bullnose Flat - Inside Corner
FULL BULLNOSE			
	RWT-09-1 Rowlock Watertable - Full Bullnose - Rowlock	RWT-09-2 Rowlock Watertable - Full Bullnose - Outside Corner	RWT-09-3 Rowlock Watertable - Full Bullnose - Inside Corner
COPING			
	RWT-10-1 Rowlock Watertable - Coping - Rowlock	RWT-10-2 Rowlock Watertable - Coping - Outside Corner	RWT-10-3 Rowlock Watertable - Coping - Inside Corner


** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Rowlock Watertable - Sloped

Table of Contents


Rowlock Gallery

RWT-01-1 Rowlock




RWT-01-1	ROWLOCK WATERTABLE - SLOPED - ROWLOCK				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/8"	2 1/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/8"	2 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 1/8"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	8 1/8"	1 1/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 1/8"	1 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	2 1/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	2 1/8"

RWT-01-2 Outside Corner



RWT-01-2	ROWLOCK WATERTABLE - SLOPED - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
KING	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"

RWT-01-3 Inside Corner




RWT-01-3	ROWLOCK WATERTABLE - SLOPED - INSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
KING	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 1/8"	1 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	2 1/8"

Rowlock Watertable - Sloped

Table of Contents

Rowlock Gallery

Wall Diagram






Rowlock Watertable - Bullnose

Table of Contents


Rowlock Gallery

RWT-02-1 Rowlock




RWT-02-1	ROWLOCK WATERTABLE - BULLNOSE - ROWLOCK				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 13/32"	3 7/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 13/32"	3 7/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 1/4"	2 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 1/4"	2 3/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 1/4"	2 3/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 13/32"	3 7/32"

RWT-02-2 Outside Corner



RWT-02-2	ROWLOCK WATERTABLE - BULLNOSE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
KING	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"

RWT-02-3 Inside Corner



RWT-02-3	ROWLOCK WATERTABLE - BULLNOSE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
KING	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 1/4"	2 3/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	13/32"	3 7/32"




Rowlock Watertable - Bullnose


Table of Contents

Rowlock Gallery


Wall Diagram




RWT-02-1




RWT-02-2




RWT-02-3




TOP VIEW




ISO VIEW



FRONT VIEW



SIDE VIEW






Rowlock Watertable - Cove

Table of Contents


Rowlock Gallery

RWT-03-1 Rowlock




RWT-03-1	ROWLOCK WATERTABLE - COVE - ROWLOCK					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 7/32"	1 7/32"	2 13/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 7/32"	1 7/32"	2 13/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/8"	7/8"	1 3/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"

RWT-03-2 Outside Corner



RWT-03-2	ROWLOCK WATERTABLE - COVE - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
KING	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"

RWT-03-3 Inside Corner



RWT-03-3	ROWLOCK WATERTABLE - COVE - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
KING	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 7/8"	7/8"	1 3/4"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 7/32"	1 7/32"	2 13/32"




Rowlock Watertable - Cove

Table of Contents

Rowlock Gallery


Wall Diagram




RWT-03-1




RWT-03-2




RWT-03-3




TOP VIEW




ISO VIEW



FRONT VIEW



SIDE VIEW






Rowlock Watertable - Ogee

Table of Contents


Rowlock Gallery

RWT-04-1 Rowlock




RWT-04-1	ROWLOCK WATERTABLE - OGEE - ROWLOCK				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 3/8"	2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 3/8"	2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6"	1 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	8"	1 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8"	1 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 3/8"	2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 3/8"	2"

RWT-04-2 Outside Corner



RWT-04-2	ROWLOCK WATERTABLE - OGEE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
KING	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"

RWT-04-3 Inside Corner



RWT-04-3	ROWLOCK WATERTABLE - OGEE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
KING	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2"	1 7/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 3/8"	2"




Rowlock Watertable - Ogee


Table of Contents

Rowlock Gallery


Wall Diagram




RWT-04-1




RWT-04-2




RWT-04-3




TOP VIEW




ISO VIEW



FRONT VIEW




SIDE VIEW



Air Gap


Consult Engineer for required structure.

RWT-05-1 Rowlock




RWT-05-1	ROWLOCK WATERTABLE - BULLNOSE OGEE - ROWLOCK						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/2"	1 1/8"	3"	6 21/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/2"	1 1/8"	3"	10 21/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 13/16"	13/16"	2 3/16"	6 15/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 13/16"	13/16"	2 3/16"	8 15/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 13/16"	13/16"	2 3/16"	8 15/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/2"	1 1/8"	3"	6 21/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/2"	1 1/8"	3"	10 21/32"

RWT-05-2 Outside Corner




RWT-05-2	ROWLOCK WATERTABLE - BULLNOSE OGEE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"

RWT-05-3 Inside Corner



RWT-05-3	ROWLOCK WATERTABLE - BULLNOSE OGEE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 13/16"	13/16"	2 3/16"	2 15/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/2"	1 1/8"	3"	2 21/32"

Wall Diagram






Rowlock Watertable - Cove Ogee

Table of Contents


Rowlock Gallery

RWT-06-1 Rowlock




RWT-06-1	ROWLOCK WATERTABLE - COVE OGEE - ROWLOCK						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 3/4"	3/4"	1 5/16"	1 9/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 3/4"	3/4"	1 5/16"	1 9/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 9/16"	9/16"	15/16"	1 1/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 9/16"	9/16"	15/16"	1 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 3/4"	3/4"	1 5/16"	1 9/16"

RWT-06-2 Outside Corner



RWT-06-2	ROWLOCK WATERTABLE - COVE OGEE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
NORMAN	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"

RWT-06-3 Inside Corner



RWT-06-3	ROWLOCK WATERTABLE - COVE OGEE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
NORMAN	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 9/16"	9/16"	15/16"	1 1/8"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	3/4"	3/4"	1 5/16"	1 9/16"




Rowlock Watertable - Cove Ogee

Table of Contents

Rowlock Gallery


Wall Diagram




RWT-06-1




RWT-06-2




RWT-06-3




TOP VIEW




ISO VIEW



FRONT VIEW



SIDE VIEW






Rowlock Watertable - Crown Ogee


[Table of Contents](#)
[Rowlock Gallery](#)

RWT-07-1 Rowlock




RWT-07-1	ROWLOCK WATERTABLE - CROWN OGEE - ROWLOCK							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 11/16"	9/16"	15/16"	1 1/2"	5 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 11/16"	9/16"	15/16"	1 1/2"	9 5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 15/16"	13/32"	11/16"	1 3/32"	6 3/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 15/16"	13/32"	11/16"	1 3/32"	8 3/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 15/16"	13/32"	11/16"	1 3/32"	8 3/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 11/16"	9/16"	15/16"	1 1/2"	5 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 11/16"	9/16"	15/16"	1 1/2"	9 5/8"

RWT-07-2 Outside Corner



RWT-07-2	ROWLOCK WATERTABLE - CROWN OGEE - OUTSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"

RWT-07-3 Inside Corner







RWT-07-3	ROWLOCK WATERTABLE - CROWN OGEE - INSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 15/16"	13/32"	11/16"	1 3/32"	2 3/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 11/16"	9/16"	15/16"	1 1/2"	1 5/8"




Rowlock Watertable - Crown Ogee

[Table of Contents](#)
[Rowlock Gallery](#)


Wall Diagram




TOP VIEW




ISO VIEW



FRONT VIEW



SIDE VIEW






Rowlock Watertable - Bullnose Flat


[Table of Contents](#)[Rowlock Gallery](#)

RWT-08-1 Rowlock




RWT-08-1	ROWLOCK WATERTABLE - BULLNOSE FLAT - ROWLOCK					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 5/8"	5/8"	3"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 5/8"	5/8"	3"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/16"	7/16"	2 3/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/16"	7/16"	2 3/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/16"	7/16"	2 3/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 5/8"	5/8"	3"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 5/8"	5/8"	3"

RWT-08-2 Outside Corner



RWT-08-2	ROWLOCK WATERTABLE - BULLNOSE FLAT - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
NORMAN	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
KING	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
UTILITY	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"

RWT-08-3 Inside Corner





RWT-08-3	ROWLOCK WATERTABLE - BULLNOSE FLAT - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
NORMAN	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
QUEEN	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
KING	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	1 7/16"	7/16"	2 3/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"
UTILITY	3 5/8"	3 5/8"	3 5/8"	5/8"	5/8"	3"



Rowlock Watertable - Bullnose Flat


[Table of Contents](#)[Rowlock Gallery](#)

Wall Diagram



TOP VIEW

ISO VIEW



FRONT VIEW

SIDE VIEW

Air Gap


Consult Engineer for required structure.



Rowlock Watertable - Full Bullnose


[Table of Contents](#)
[Rowlock Gallery](#)

RWT-09-1 Rowlock




RWT-09-1	ROWLOCK WATERTABLE - FULL BULLNOSE - ROWLOCK						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/8"	5/8"	1 1/2"	6 1/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/8"	5/8"	1 1/2"	10 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 17/32"	7/16"	1 3/32"	6 17/32"
KING	2 5/8"	9 5/8"	2 5/8"	8 17/32"	7/16"	1 3/32"	8 17/32"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 17/32"	7/16"	1 3/32"	8 17/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	5/8"	1 1/2"	6 1/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	5/8"	1 1/2"	10 1/8"

RWT-09-2 Outside Corner



RWT-09-2	ROWLOCK WATERTABLE - FULL BULLNOSE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
KING	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"

RWT-09-3 Inside Corner




RWT-09-3	ROWLOCK WATERTABLE - FULL BULLNOSE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
NORMAN	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
KING	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 17/32"	7/16"	1 3/32"	2 17/32"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"
UTILITY	3 5/8"	3 5/8"	3 5/8"	2 1/8"	5/8"	1 1/2"	2 1/8"



Rowlock Watertable - Full Bullnose

[Table of Contents](#)
[Rowlock Gallery](#)

Wall Diagram




Rowlock Watertable - Coping

Table of Contents


Rowlock Gallery

RWT-10-1 Rowlock




RWT-10-1	ROWLOCK WATERTABLE - COPING - ROWLOCK				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 13/16"	1 13/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 13/16"	1 13/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 5/16"	1 5/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 5/16"	1 5/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 5/16"	1 5/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 13/16"	1 13/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 13/16"	1 13/16"

RWT-10-2 Outside Corner



RWT-10-2	ROWLOCK WATERTABLE - COPING - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"

RWT-10-3 Inside Corner





RWT-10-3	ROWLOCK WATERTABLE - COPING - INSIDE CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
NORMAN	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
QUEEN	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
KING	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
ESTATE	2 5/8"	3 5/8"	3 5/8"	2 5/16"	1 5/16"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"
UTILITY	3 5/8"	3 5/8"	3 5/8"	1 13/16"	1 13/16"

Rowlock Watertable - Coping


Table of Contents

Rowlock Gallery


Wall Diagram




TOP VIEW



ISO VIEW



FRONT VIEW



SIDE VIEW




Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Window Sills































SLOPED			
	WSL-01-1 Window Sill - Sloped	WSL-01-2 Window Sill - Sloped Left	WSL-01-3 Window Sill - Sloped Right
BULLNOSE			
	WSL-02-1 Window Sill - Bullnose	WSL-02-2 Window Sill - Bullnose Left	WSL-02-3 Window Sill - Bullnose Right
COVE			
	WSL-03-1 Window Sill - Cove	WSL-03-2 Window Sill - Cove Left	WSL-03-3 Window Sill - Cove Right
OGEE			
	WSL-04-1 Window Sill - Ogee	WSL-04-2 Window Sill - Ogee Left	WSL-04-3 Window Sill - Ogee Right
BULLNOSE OGEE			
	WSL-05-1 Window Sill - Bullnose Ogee	WSL-05-2 Window Sill - Bullnose Ogee Left	WSL-05-3 Window Sill - Bullnose Ogee Right

Table of Contents

Click on any shape for more details.

Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Window Sills (Continued)

COVE OGEE			
	WSL-06-1 Window Sill - Cove Ogee	WSL-06-2 Window Sill - Cove Ogee Left	WSL-06-3 Window Sill - Cove Ogee Right
CROWN OGEE			
	WSL-07-1 Window Sill - Crown Ogee	WSL-07-2 Window Sill - Crown Ogee Left	WSL-07-3 Window Sill - Crown Ogee Right
BULLNOSE FLAT			
	WSL-08-1 Window Sill - Bullnose Flat	WSL-08-2 Window Sill - Bullnose Flat Left	WSL-08-3 Window Sill - Bullnose Flat Right
FULL BULLNOSE			
	WSL-09-1 Window Sill - Full Bullnose	WSL-09-2 Window Sill - Full Bullnose Left	WSL-09-3 Window Sill - Full Bullnose Right
COPING			
	WSL-10-1 Window Sill - Coping	WSL-10-2 Window Sill - Coping Left	WSL-10-3 Window Sill - Coping Right




Window Sills - Sloped

Table of Contents


Sills Gallery

WSL-01-1 Window Sill




WSL-01-1	WINDOW SILL - SLOPED				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 1/4"	1 1/4"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 1/4"	1 1/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 13/16"	13/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 13/16"	13/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 13/16"	13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 1/4"	1 1/4"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 1/4"	1 1/4"

WSL-01-2 Left



WSL-01-2	WINDOW SILL - SLOPED - LEFT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 1/4"	1 1/4"	5 7/8"	4 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 1/4"	1 1/4"	9 7/8"	4 5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 13/16"	13/16"	6 9/32"	4 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 13/16"	13/16"	8 9/32"	4 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 13/16"	13/16"	8 9/32"	5 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 1/4"	1 1/4"	5 7/8"	6"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 1/4"	1 1/4"	9 7/8"	6"

WSL-01-3 Right



WSL-01-3	WINDOW SILL - SLOPED - RIGHT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 1/4"	1 1/4"	5 7/8"	4 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 1/4"	1 1/4"	9 7/8"	4 5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 13/16"	13/16"	6 9/32"	4 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 13/16"	13/16"	8 9/32"	4 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 13/16"	13/16"	8 9/32"	5 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 1/4"	1 1/4"	5 7/8"	6"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 1/4"	1 1/4"	9 7/8"	6"




Window Sills - Sloped

Table of Contents

Sills Gallery

Window Diagram






Window Sills - Bullnose

Table of Contents


Sills Gallery

WSL-02-1 Window Sill




WSL-02-1	WINDOW SILL - BULLNOSE				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 13/32"	3 7/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 13/32"	3 7/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 1/4"	2 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 1/4"	2 3/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 1/4"	2 3/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 13/32"	3 7/32"

WSL-02-2 Left



WSL-02-2	WINDOW SILL - BULLNOSE - LEFT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 13/32"	3 7/32"	5 1/16"	5 15/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 13/32"	3 7/32"	9 1/16"	5 15/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 1/4"	2 3/8"	5 23/32"	5"
KING	2 5/8"	9 5/8"	2 5/8"	7 1/4"	2 3/8"	7 23/32"	5"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 1/4"	2 3/8"	7 23/32"	6"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 13/32"	3 7/32"	5 1/16"	6 27/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 13/32"	3 7/32"	9 1/16"	6 27/32"

WSL-02-3 Right



WSL-02-3	WINDOW SILL - BULLNOSE - RIGHT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 13/32"	3 7/32"	5 1/16"	5 15/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 13/32"	3 7/32"	9 1/16"	5 15/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 1/4"	2 3/8"	5 23/32"	5"
KING	2 5/8"	9 5/8"	2 5/8"	7 1/4"	2 3/8"	7 23/32"	5"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 1/4"	2 3/8"	7 23/32"	6"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 13/32"	3 7/32"	5 1/16"	6 27/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 13/32"	3 7/32"	9 1/16"	6 27/32"




Window Sills - Bullnose

Table of Contents

Sills Gallery

Window Diagram






Window Sills - Cove

Table of Contents


Sills Gallery

WSL-03-1 Window Sill




WSL-03-1	WINDOW SILL - COVE					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 7/32"	1 7/32"	2 13/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 7/32"	1 7/32"	2 13/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/8"	7/8"	1 3/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"

WSL-03-2 Left



WSL-03-2	WINDOW SILL - COVE - LEFT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 7/32"	1 7/32"	2 13/32"	5 11/32"	4 21/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 7/32"	1 7/32"	2 13/32"	9 11/32"	4 21/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"	5 31/32"	4 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"	7 31/32"	4 3/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/8"	7/8"	1 3/4"	7 31/32"	5 3/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"	5 11/32"	6 1/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"	6 1/32"	6 1/32"

WSL-03-3 Right



WSL-03-3	WINDOW SILL - COVE - RIGHT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 7/32"	1 7/32"	2 13/32"	5 11/32"	4 21/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 7/32"	1 7/32"	2 13/32"	9 11/32"	4 21/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"	5 31/32"	4 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"	7 31/32"	4 3/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/8"	7/8"	1 3/4"	7 31/32"	5 3/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"	5 11/32"	6 1/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"	6 1/32"	6 1/32"





Window Sills - Cove

Table of Contents

Sills Gallery

Window Diagram






Window Sills - Ogee

Table of Contents


Sills Gallery

WSL-04-1 Window Sill




WSL-04-1	WINDOW SILL - OGEE				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 3/8"	2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 3/8"	2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6"	1 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	8"	1 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8"	1 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 3/8"	2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 3/8"	2"

WSL-04-2 Left



WSL-04-2	WINDOW SILL - OGEE - LEFT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 3/8"	2"	5 19/32"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 3/8"	2"	9 19/32"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6"	1 7/16"	6 5/32"	4 1/4"
KING	2 5/8"	9 5/8"	2 5/8"	8"	1 7/16"	8 5/32"	4 1/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8"	1 7/16"	8 5/32"	5 1/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 3/8"	2"	5 19/32"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 3/8"	2"	9 19/32"	5 7/8"

WSL-04-3 Right



WSL-04-3	WINDOW SILL - OGEE - RIGHT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 3/8"	2"	5 19/32"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 3/8"	2"	9 19/32"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6"	1 7/16"	6 5/32"	4 1/4"
KING	2 5/8"	9 5/8"	2 5/8"	8"	1 7/16"	8 5/32"	4 1/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8"	1 7/16"	8 5/32"	5 1/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 3/8"	2"	5 19/32"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 3/8"	2"	9 19/32"	5 7/8"






Window Sills - Ogee

Table of Contents

Sills Gallery

Window Diagram



Sills can be laid between ~5° and ~15° off horizontal to allow for variation in window frame elevation.

All Cut Outs are 80° on Sill Ends, which gives you a 10° Sill Angle. Window Height is equal to "A".

Rotated Down 5° so Sill meets a Longer Window Frame. Window Height is Greater than "A".

Rotated Up 5° so Sill meets a Shorter Window Frame. Window Height is Smaller than "A".




Window Sills - Bullnose Ogee

Table of Contents


Sills Gallery

WSL-05-1 Window Sill




WSL-05-1	WINDOW SILL - BULLNOSE OGEE						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/2"	1 1/8"	3"	6 21/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/2"	1 1/8"	3"	10 21/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 13/16"	13/16"	2 3/16"	6 15/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 13/16"	13/16"	2 3/16"	8 15/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 13/16"	13/16"	2 3/16"	8 15/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/2"	1 1/8"	3"	6 21/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/2"	1 1/8"	3"	10 21/32"

WSL-05-2 Left



WSL-05-2	WINDOW SILL - BULLNOSE OGEE - LEFT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/2"	1 1/8"	3"	6 5/32"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/2"	1 1/8"	3"	10 5/32"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 13/16"	13/16"	2 3/16"	6 9/16"	4 1/4"
KING	2 5/8"	9 5/8"	2 5/8"	8 13/16"	13/16"	2 3/16"	8 9/16"	4 1/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 13/16"	13/16"	2 3/16"	8 9/16"	5 1/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/2"	1 1/8"	3"	6 5/32"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/2"	1 1/8"	3"	10 5/32"	5 7/8"

WSL-05-3 Right



WSL-05-3	WINDOW SILL - BULLNOSE OGEE - RIGHT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/2"	1 1/8"	3"	6 5/32"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/2"	1 1/8"	3"	10 5/32"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 13/16"	13/16"	2 3/16"	6 9/16"	4 1/4"
KING	2 5/8"	9 5/8"	2 5/8"	8 13/16"	13/16"	2 3/16"	8 9/16"	4 1/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 13/16"	13/16"	2 3/16"	8 9/16"	5 1/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/2"	1 1/8"	3"	6 5/32"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/2"	1 1/8"	3"	10 5/32"	5 7/8"




Window Sills - Bullnose Ogee

Table of Contents

Sills Gallery

Window Diagram






Window Sills - Cove Ogee

Table of Contents


Sills Gallery

WSL-06-1 Window Sill




WSL-06-1	WINDOW SILL - COVE OGEE						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 3/4"	3/4"	1 5/16"	1 9/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 3/4"	3/4"	1 5/16"	1 9/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 9/16"	9/16"	15/16"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	7 9/16"	9/16"	15/16"	1 1/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 9/16"	9/16"	15/16"	1 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 3/4"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 3/4"	3/4"	1 5/16"	1 9/16"

WSL-06-2 Left



WSL-06-2	WINDOW SILL - COVE OGEE - LEFT								
	A	B	C	D	E	F	G	H	I
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 3/4"	3/4"	1 5/16"	1 9/16"	4 29/32"	5 1/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 3/4"	3/4"	1 5/16"	1 9/16"	8 29/32"	5 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 9/16"	9/16"	15/16"	1 1/8"	5 21/32"	4 11/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 9/16"	9/16"	15/16"	1 1/8"	7 21/32"	4 11/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 9/16"	9/16"	15/16"	1 1/8"	7 21/32"	5 11/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 3/4"	3/4"	1 5/16"	1 9/16"	4 29/32"	6 1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 3/4"	3/4"	1 5/16"	1 9/16"	8 29/32"	6 1/2"

WSL-06-3 Right



WSL-06-3	WINDOW SILL - COVE OGEE - RIGHT								
	A	B	C	D	E	F	G	H	I
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 3/4"	3/4"	1 5/16"	1 9/16"	4 29/32"	5 1/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 3/4"	3/4"	1 5/16"	1 9/16"	8 29/32"	5 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 9/16"	9/16"	15/16"	1 1/8"	5 21/32"	4 11/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 9/16"	9/16"	15/16"	1 1/8"	7 21/32"	4 11/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 9/16"	9/16"	15/16"	1 1/8"	7 21/32"	5 11/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 3/4"	3/4"	1 5/16"	1 9/16"	4 29/32"	6 1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 3/4"	3/4"	1 5/16"	1 9/16"	8 29/32"	6 1/2"









Window Sills - Cove Ogee

Table of Contents

Sills Gallery

Window Diagram



Sills can be laid between ~5° and ~15° off horizontal to allow for variation in window frame elevation.

All Cut Outs are 80° on Sill Ends, which gives you a 10° Sill Angle. Window Height is equal to "A".

Rotated Down 5° so Sill meets a Longer Window Frame. Window Height is Greater than "A".


Rotated Up 5° so Sill meets a Shorter Window Frame. Window Height is Smaller than "A".

Window Sills - Crown Ogee

Table of Contents


Sills Gallery

WSL-07-1 Window Sill




WSL-07-1	WINDOW SILL - CROWN OGEE							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 15/16"	13/32"	11/16"	1 3/8"	5 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"

WSL-07-2 Left



WSL-07-2	WINDOW SILL - CROWN OGEE - LEFT								
	A	B	C	D	E	F	G	H	I
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"	4 27/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"	4 27/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 15/16"	13/32"	11/16"	1 3/8"	5 3/4"	4 1/2"
KING	2 5/8"	9 5/8"	2 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"	4 1/2"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"	5 1/2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"	6 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"	6 7/32"

WSL-07-3 Right




WSL-07-3	WINDOW SILL - CROWN OGEE - RIGHT								
	A	B	C	D	E	F	G	H	I
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"	4 27/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"	4 27/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 15/16"	13/32"	11/16"	1 3/8"	5 3/4"	4 1/2"
KING	2 5/8"	9 5/8"	2 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"	4 1/2"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 15/16"	13/32"	11/16"	1 3/8"	7 3/4"	5 1/2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 11/16"	9/16"	15/16"	1 29/32"	5 1/32"	6 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 11/16"	9/16"	15/16"	1 29/32"	9 1/32"	6 7/32"

Window Sills - Crown Ogee

Table of Contents

Sills Gallery

Window Diagram




WSL-07-2




WSL-07-1




WSL-07-3



TOP VIEW




ISO VIEW



FRONT VIEW

Sills can be laid between ~5° and ~15° off horizontal to allow for variation in window frame elevation.



SIDE VIEW

All Cut Outs are 80° on Sill Ends, which gives you a 10° Sill Angle. Window Height is equal to "A".

SIDE VIEW

Rotated Down 5° so Sill meets a Longer Window Frame. Window Height is Greater than "A".

SIDE VIEW

Rotated Up 5° so Sill meets a Shorter Window Frame. Window Height is Smaller than "A".




Window Sills - Bullnose Flat

Table of Contents


Sills Gallery

WSL-08-1 Window Sill




WSL-08-1	WINDOW SILL - BULLNOSE FLAT					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 5/8"	5/8"	3"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 5/8"	5/8"	3"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/16"	7/16"	2 3/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/16"	7/16"	2 3/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/16"	7/16"	2 3/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 5/8"	5/8"	3"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 5/8"	5/8"	3"

WSL-08-2 Left



WSL-08-2	WINDOW SILL - BULLNOSE FLAT - LEFT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 5/8"	5/8"	3"	4 25/32"	5 1/4"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 5/8"	5/8"	3"	8 25/32"	5 1/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/16"	7/16"	2 3/16"	5 7/16"	4 13/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/16"	7/16"	2 3/16"	7 7/16"	4 13/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/16"	7/16"	2 3/16"	7 7/16"	5 13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 5/8"	5/8"	3"	4 25/32"	6 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 5/8"	5/8"	3"	8 25/32"	6 5/8"

WSL-08-3 Right



WSL-08-3	WINDOW SILL - BULLNOSE FLAT - RIGHT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	4 5/8"	5/8"	3"	4 25/32"	5 1/4"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 5/8"	5/8"	3"	8 25/32"	5 1/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	5 7/16"	7/16"	2 3/16"	5 7/16"	4 13/16"
KING	2 5/8"	9 5/8"	2 5/8"	7 7/16"	7/16"	2 3/16"	7 7/16"	4 13/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	7 7/16"	7/16"	2 3/16"	7 7/16"	5 13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	4 5/8"	5/8"	3"	4 25/32"	6 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 5/8"	5/8"	3"	8 25/32"	6 5/8"







Window Sills - Bullnose Flat


Table of Contents

Sills Gallery


Window Diagram



TOP VIEW



ISO VIEW



FRONT VIEW

SIDE VIEW

SIDE VIEW

SIDE VIEW

Sills can be laid between ~5° and ~15° off horizontal to allow for variation in window frame elevation.

All Cut Outs are 80° on Sill Ends, which gives you a 10° Sill Angle. Window Height is equal to "A".

Rotated Down 5° so Sill meets a Longer Window Frame. Window Height is Greater than "A".

Rotated Up 5° so Sill meets a Shorter Window Frame. Window Height is Smaller than "A".




Window Sills - Full Bullnose

Table of Contents


Sills Gallery

WSL-09-1 Window Sill




WSL-09-1	WINDOW SILL - FULL BULLNOSE						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/8"	5/8"	1 1/2"	6 1/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/8"	5/8"	1 1/2"	10 1/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 17/32"	7/16"	1 3/32"	6 17/32"
KING	2 5/8"	9 5/8"	2 5/8"	8 17/32"	7/16"	1 3/32"	8 17/32"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 17/32"	7/16"	1 3/32"	8 17/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	5/8"	1 1/2"	6 1/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	5/8"	1 1/2"	10 1/8"

WSL-09-2 Left



WSL-09-2	WINDOW SILL - FULL BULLNOSE - LEFT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/8"	5/8"	1 1/2"	5 5/8"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/8"	5/8"	1 1/2"	9 5/8"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 17/32"	7/16"	1 3/32"	6 1/32"	4 15/32"
KING	2 5/8"	9 5/8"	2 5/8"	8 17/32"	7/16"	1 3/32"	8 1/32"	4 15/32"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 17/32"	7/16"	1 3/32"	8 1/32"	5 15/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	5/8"	1 1/2"	5 5/8"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	5/8"	1 1/2"	9 5/8"	5 7/8"

WSL-09-3 Right



WSL-09-3	WINDOW SILL - FULL BULLNOSE - RIGHT							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	2 1/4"	6 1/8"	5/8"	1 1/2"	5 5/8"	4 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	10 1/8"	5/8"	1 1/2"	9 5/8"	4 1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 17/32"	7/16"	1 3/32"	6 1/32"	4 15/32"
KING	2 5/8"	9 5/8"	2 5/8"	8 17/32"	7/16"	1 3/32"	8 1/32"	4 15/32"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 17/32"	7/16"	1 3/32"	8 1/32"	5 15/32"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	6 1/8"	5/8"	1 1/2"	5 5/8"	5 7/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	10 1/8"	5/8"	1 1/2"	9 5/8"	5 7/8"




Window Sills - Full Bullnose

Table of Contents

Sills Gallery

Window Diagram




Window Sills - Coping

Table of Contents


Sills Gallery

WSL-10-1 Window Sill




WSL-10-1	WINDOW SILL - COPING				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 13/16"	1 13/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 13/16"	1 13/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 5/16"	1 5/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 5/16"	1 5/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 5/16"	1 5/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 13/16"	1 13/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 13/16"	1 13/16"

WSL-10-2 Left



WSL-10-2	WINDOW SILL - COPING - LEFT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 13/16"	1 13/16"	4 1/2"	4 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 13/16"	1 13/16"	4 1/2"	4 5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 5/16"	1 5/16"	4 1/2"	4 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 5/16"	1 5/16"	4 1/2"	4 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 5/16"	1 5/16"	5 1/2"	5 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 13/16"	1 13/16"	5 7/8"	6"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 13/16"	1 13/16"	5 7/8"	6"

WSL-10-3 Right



WSL-10-3	WINDOW SILL - COPING - RIGHT						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	5 13/16"	1 13/16"	4 1/2"	4 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 13/16"	1 13/16"	4 1/2"	4 5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	6 5/16"	1 5/16"	4 1/2"	4 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	8 5/16"	1 5/16"	4 1/2"	4 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	8 5/16"	1 5/16"	5 1/2"	5 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	5 13/16"	1 13/16"	5 7/8"	6"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 13/16"	1 13/16"	5 7/8"	6"

Window Sills - Coping

Table of Contents

Sills Gallery

Window Diagram





Table of Contents

Click on any shape for more details.


Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Rowlock Wall Caps

SLOPED




RWC-01-1
Rowlock Wall Cap - Sloped




RWC-01-2
Rowlock Wall Cap - Sloped - End

BULLNOSE




RWC-02-1
Rowlock Wall Cap - Bullnose




RWC-02-2
Rowlock Wall Cap - Bullnose - End

COVE




RWC-03-1
Rowlock Wall Cap - Cove




RWC-03-2
Rowlock Wall Cap - Cove - End

OGEЕ




RWC-04-1
Rowlock Wall Cap - Ogee




RWC-04-2
Rowlock Wall Cap - Ogee - End

BULLNOSE OGEЕ



RWC-05-1
Rowlock Wall Cap - Bullnose Ogee



RWC-05-2
Rowlock Wall Cap - Bullnose Ogee - End


Table of Contents

Click on any shape for more details.


Shape Nomenclature: [Shape Type Code]-[Profile]-[Piece]

Rowlock Wall Caps (Continued)

COVE OGEЕ




RWC-06-1
Rowlock Wall Cap - Cove Ogee




RWC-06-2
Rowlock Wall Cap - Cove Ogee - End

CROWN OGEЕ




RWC-07-1
Rowlock Wall Cap - Crown Ogee




RWC-07-2
Rowlock Wall Cap - Crown Ogee - End

BULLNOSE FLAT




RWC-08-1
Rowlock Wall Cap - Bullnose Flat




RWC-08-2
Rowlock Wall Cap - Bullnose Flat - End

FULL BULLNOSE




RWC-09-1 Rowlock Wall Cap - Full Bullnose




RWC-09-2 Rowlock Wall Cap - Full Bullnose - End

COPING



RWC-10-1 Rowlock Wall Cap - Coping



RWC-10-2 Rowlock Wall Cap - Coping - End




Rowlock Wall Caps - Sloped

Table of Contents


Wall Cap Gallery

RWC-01-1 Wall Cap





RWC-01-1	ROWLOCK WALL CAP - SLOPED				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	2 7/8"	1 1/4"
NORMAN	3 5/8"	11 5/8"	2 1/4"	6 7/8"	1 1/4"
QUEEN	2 5/8"	7 5/8"	2 5/8"	4"	13/16"
KING	2 5/8"	9 5/8"	2 5/8"	6"	13/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6"	13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	2 7/8"	1 1/4"
UTILITY	3 5/8"	11 5/8"	3 5/8"	6 7/8"	1 1/4"

RWC-01-2 End



RWC-01-2	ROWLOCK WALL CAP - SLOPED - END					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	3 5/8"	2 7/8"	1 1/4"	1 1/4"
NORMAN	3 5/8"	11 5/8"	3 5/8"	6 7/8"	1 1/4"	1 1/4"
QUEEN	2 5/8"	7 5/8"	3 5/8"	4"	13/16"	1 13/16"
KING	2 5/8"	9 5/8"	3 5/8"	6"	13/16"	1 13/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6"	13/16"	1 13/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	2 7/8"	1 1/4"	1 1/4"
UTILITY	3 5/8"	11 5/8"	3 5/8"	6 7/8"	1 1/4"	1 1/4"

Sloped Wall Cap Diagram














Rowlock Wall Caps - Sloped

Table of Contents

Wall Cap Gallery

Other Sloped Wall Cap Options (using other shapes)






Rowlock Wall Caps - Bullnose

Table of Contents


Wall Cap Gallery

RWC-02-1 Wall Cap




RWC-02-1	ROWLOCK WALL CAP - BULLNOSE				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	1 3/16"	3 7/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	5 3/16"	3 7/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	2 7/8"	2 3/8"
KING	2 5/8"	9 5/8"	2 5/8"	4 7/8"	2 3/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	4 7/8"	2 3/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 3/16"	3 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 3/16"	3 7/32"

RWC-02-2 End



RWC-02-2	ROWLOCK WALL CAP - BULLNOSE - END					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	1 3/16"	3 7/32"	13/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	5 3/16"	3 7/32"	13/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	2 7/8"	2 3/8"	1 1/4"
KING	2 5/8"	9 5/8"	2 5/8"	4 7/8"	2 3/8"	1 1/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	4 7/8"	2 3/8"	1 1/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 3/16"	3 7/32"	13/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 3/16"	3 7/32"	13/32"

Bullnose Wall Cap Diagram




TOP VIEW

FRONT VIEW



SIDE VIEW



RWC-02-1

RWC-02-2

ISO VIEW




Rowlock Wall Caps - Bullnose


Table of Contents

Wall Cap Gallery


Other Bullnose Wall Cap Options



TOP VIEW




FRONT VIEW




SIDE VIEW


profile only
on one side




ISO VIEW




RWT-02-1
Watertable Bullnose
Rowlock



TOP VIEW




FRONT VIEW




SIDE VIEW

profile on both
sides with joint
on top




ISO VIEW




*Field Cut
RWT-02-1
Watertable Bullnose
Rowlock




RWC-02-2 Bullnose
Wall Cap End



TOP VIEW




FRONT VIEW




SIDE VIEW


profile on
both sides
for wider walls




ISO VIEW



RWT-02-1
Watertable Bullnose
Rowlock



*Field Cut
RWT-02-1
Watertable Bullnose
Rowlock



*Field Cut
RWC-02-2 Bullnose
Wall Cap End




Rowlock Wall Cap - Cove

Table of Contents


Wall Cap Gallery

RWC-03-1 Wall Cap




RWC-03-1	ROWLOCK WALL CAP - COVE					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	2 25/32"	1 7/32"	2 13/32"
NORMAN	3 5/8"	11 5/8"	2 1/4"	6 25/32"	1 7/32"	2 13/32"
QUEEN	2 5/8"	7 5/8"	2 5/8"	4 1/8"	7/8"	1 3/4"
KING	2 5/8"	9 5/8"	2 5/8"	6 1/8"	7/8"	1 3/4"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6 1/8"	7/8"	1 3/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	2 25/32"	1 7/32"	2 13/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	6 25/32"	1 7/32"	2 13/32"

RWC-03-2 End




RWC-03-2	ROWLOCK WALL CAP - COVE - END						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	3 5/8"	2 25/32"	1 7/32"	2 13/32"	1 7/32"
NORMAN	3 5/8"	11 5/8"	3 5/8"	6 25/32"	1 7/32"	2 13/32"	1 7/32"
QUEEN	2 5/8"	7 5/8"	3 5/8"	4 1/8"	7/8"	1 3/4"	1 7/8"
KING	2 5/8"	9 5/8"	3 5/8"	6 1/8"	7/8"	1 3/4"	1 7/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6 1/8"	7/8"	1 3/4"	1 7/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	2 25/32"	1 7/32"	2 13/32"	1 7/32"
UTILITY	3 5/8"	11 5/8"	3 5/8"	6 25/32"	1 7/32"	2 13/32"	1 7/32"


Cove Wall Cap Diagram




TOP VIEW



FRONT VIEW



SIDE VIEW



RWC-03-1

RWC-03-2




Rowlock Wall Cap - Cove


Table of Contents

Wall Cap Gallery


Other Cove Wall Cap Options



TOP VIEW




FRONT VIEW



SIDE VIEW


profile only
on one side




ISO VIEW



RWT-03-1
Watertable Cove
Rowlock



TOP VIEW




FRONT VIEW




SIDE VIEW

profile on both
sides with joint
on top




ISO VIEW




*Field Cut
RWT-03-1
Watertable Cove
Rowlock



RWC-03-2 Cove
Wall Cap End



TOP VIEW




FRONT VIEW




SIDE VIEW


profile on
both sides
for wider walls




ISO VIEW



RWT-03-1
Watertable Cove
Rowlock



*Field Cut
RWT-03-1
Watertable Cove
Rowlock



*Field Cut
RWC-03-2 Cove
Wall Cap End




Rowlock Wall Caps - Ogee

Table of Contents


Wall Cap Gallery

RWC-04-1 Wall Cap




RWC-04-1	ROWLOCK WALL CAP - OGEE				
	A	B	C	D	E
MODULAR	3 5/8"	7 5/8"	2 1/4"	3 1/8"	2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	7 1/8"	2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	4 3/8"	1 7/16"
KING	2 5/8"	9 5/8"	2 5/8"	6 3/8"	1 7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6 3/8"	1 7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3 1/8"	2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	7 1/8"	2"

RWC-04-2 End




RWC-04-2	ROWLOCK WALL CAP - OGEE - END					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	3 5/8"	3 1/8"	2"	1 3/8"
NORMAN	3 5/8"	11 5/8"	3 5/8"	7 1/8"	2"	1 3/8"
QUEEN	2 5/8"	7 5/8"	3 5/8"	4 3/8"	1 7/16"	2"
KING	2 5/8"	9 5/8"	3 5/8"	6 3/8"	1 7/16"	2"
ESTATE	2 5/8"	9 5/8"	3 5/8"	6 3/8"	1 7/16"	2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3 1/8"	2"	1 3/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	7 1/8"	2"	1 3/8"

Ogee Wall Cap Diagram




TOP VIEW

FRONT VIEW



SIDE VIEW



RWC-04-1

RWC-04-2




Rowlock Wall Caps - Ogee


Table of Contents

Wall Cap Gallery


Other Ogee Wall Cap Options



TOP VIEW




FRONT VIEW




SIDE VIEW


profile only
on one side




ISO VIEW




RWT-04-1
Watertable Ogee
Rowlock



TOP VIEW




FRONT VIEW




SIDE VIEW

profile on both
sides with joint
on top




ISO VIEW




RWT-04-1
Watertable Ogee
Rowlock
**Field Cut*




RWC-04-2 Ogee
Wall Cap End



TOP VIEW




FRONT VIEW




SIDE VIEW


profile on
both sides
for wider walls




ISO VIEW



RWT-04-1
Watertable Ogee
Rowlock
**Field Cut*



RWT-04-1
Watertable Ogee
Rowlock
**Field Cut*




RWC-04-2 Ogee
Wall Cap End
**Field Cut*



Rowlock Wall Caps - Bullnose Ogee

[Table of Contents](#)
[Wall Cap Gallery](#)



RWC-05-1 Wall Cap





RWC-05-1	ROWLOCK WALL CAP - BULLNOSE OGEE						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	9 17/32"	2 1/4"	7 9/32"	1 1/8"	3"	7 5/8"
NORMAN	3 5/8"	11 17/32"	2 1/4"	9 9/32"	1 1/8"	3"	9 5/8"
QUEEN	2 5/8"	9"	2 5/8"	7 3/8"	13/16"	2 3/16"	7 5/8"
KING	2 5/8"	11"	2 5/8"	9 3/8"	13/16"	2 3/16"	9 5/8"
ESTATE	2 5/8"	11"	3 5/8"	9 3/8"	13/16"	2 3/16"	9 5/8"
CLOSURE	3 5/8"	9 17/32"	3 5/8"	7 9/32"	1 1/8"	3"	7 5/8"
UTILITY	3 5/8"	11 17/32"	3 5/8"	9 9/32"	1 1/8"	3"	9 5/8"

RWC-05-2 End

RWC-05-2	ROWLOCK WALL CAP - BULLNOSE OGEE - END								
	A	B	C	D	E	F	G	H	I
MODULAR	3 5/8"	9 17/32"	3 5/8"	7 9/32"	1 1/8"	3"	7 5/8"	4 19/32"	3 15/32"
NORMAN	3 5/8"	11 17/32"	3 5/8"	9 9/32"	1 1/8"	3"	9 5/8"	4 19/32"	3 15/32"
QUEEN	2 5/8"	9"	3 5/8"	7 3/8"	13/16"	2 3/16"	7 5/8"	4 5/16"	3 1/2"
KING	2 5/8"	11"	3 5/8"	9 3/8"	13/16"	2 3/16"	9 5/8"	4 5/16"	3 1/2"
ESTATE	2 5/8"	11"	3 5/8"	9 3/8"	13/16"	2 3/16"	9 5/8"	4 5/16"	3 1/2"
CLOSURE	3 5/8"	9 17/32"	3 5/8"	7 9/32"	1 1/8"	3"	7 5/8"	4 19/32"	3 15/32"
UTILITY	3 5/8"	11 17/32"	3 5/8"	9 9/32"	1 1/8"	3"	9 5/8"	4 19/32"	3 15/32"



Bullnose Ogee Wall Cap Diagram














Rowlock Wall Caps - Bullnose Ogee

[Table of Contents](#)
[Wall Cap Gallery](#)

Other Bullnose Ogee Wall Cap Options






Rowlock Wall Caps - Cove Ogee

Table of Contents


Wall Cap Gallery

RWC-06-1 Wall Cap





RWC-06-1	ROWLOCK WALL CAP - COVE OGEE						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	1 7/8"	3/4"	1 5/16"	1 9/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	5 7/8"	3/4"	1 5/16"	1 9/16"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3 1/2"	9/16"	15/16"	1 1/8"
KING	2 5/8"	9 5/8"	2 5/8"	5 1/2"	9/16"	15/16"	1 1/8"
ESTATE	2 5/8"	9 5/8"	3 5/8"	5 1/2"	9/16"	15/16"	1 1/8"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 7/8"	3/4"	1 5/16"	1 9/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 7/8"	3/4"	1 5/16"	1 9/16"

RWC-06-2 End



RWC-06-2	ROWLOCK WALL CAP - COVE OGEE - END							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	7 5/8"	3 5/8"	1 7/8"	3/4"	1 5/16"	1 9/16"	3/4"
NORMAN	3 5/8"	11 5/8"	3 5/8"	5 7/8"	3/4"	1 5/16"	1 9/16"	3/4"
QUEEN	2 5/8"	7 5/8"	3 5/8"	3 1/2"	9/16"	15/16"	1 1/8"	1 9/16"
KING	2 5/8"	9 5/8"	3 5/8"	5 1/2"	9/16"	15/16"	1 1/8"	1 9/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	5 1/2"	9/16"	15/16"	1 1/8"	1 9/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 7/8"	3/4"	1 5/16"	1 9/16"	3/4"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 7/8"	3/4"	1 5/16"	1 9/16"	3/4"

Cove Ogee Wall Cap Diagram
















Rowlock Wall Caps - Cove Ogee

Table of Contents

Wall Cap Gallery

Other Cove Ogee Wall Cap Options






Rowlock Wall Caps - Crown Ogee

Table of Contents

Wall Cap Gallery


RWC-07-1 Wall Cap





RWC-07-1	ROWLOCK WALL CAP - CROWN OGEE							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	11 5/8"	2 1/4"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"
QUEEN	2 5/8"	11 13/16"	2 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"
KING	2 5/8"	11 13/16"	2 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"
ESTATE	2 5/8"	11 13/16"	3 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"
CLOSURE	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"

RWC-07-2 End

RWC-07-2	ROWLOCK WALL CAP - CROWN OGEE - END									
	A	B	C	D	E	F	G	H	I	J
MODULAR	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"	5 5/8"	4 11/16"
NORMAN	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"	5 5/8"	4 11/16"
QUEEN	2 5/8"	11 13/16"	3 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"	5 1/2"	4 27/32"
KING	2 5/8"	11 13/16"	3 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"	5 1/2"	4 27/32"
ESTATE	2 5/8"	11 13/16"	3 5/8"	10 1/16"	13/32"	11/16"	1 3/8"	7 5/8"	5 1/2"	4 27/32"
CLOSURE	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"	5 5/8"	4 11/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	9 25/32"	9/16"	15/16"	1 1/2"	7 5/8"	5 5/8"	4 11/16"



Crown Ogee Wall Cap Diagram














Rowlock Wall Caps - Crown Ogee

Table of Contents

Wall Cap Gallery

Other Crown Ogee Wall Cap Options






Rowlock Wall Caps - Bullnose Flat

Table of Contents


Wall Cap Gallery

RWC-08-1 Wall Cap




RWC-08-1	ROWLOCK WALL CAP - BULLNOSE FLAT					
	A	B	C	D	E	F
MODULAR	3 5/8"	7 5/8"	2 1/4"	1 5/8"	5/8"	3"
NORMAN	3 5/8"	11 5/8"	2 1/4"	5 5/8"	5/8"	3"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3 9/32"	7/16"	2 3/16"
KING	2 5/8"	9 5/8"	2 5/8"	5 9/32"	7/16"	2 3/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	5 9/32"	7/16"	2 3/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 5/8"	5/8"	3"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 5/8"	5/8"	3"

RWC-08-2 End




RWC-08-2	ROWLOCK WALL CAP - BULLNOSE FLAT - END						
	A	B	C	D	E	F	G
MODULAR	3 5/8"	7 5/8"	2 1/4"	1 5/8"	5/8"	3"	5/8"
NORMAN	3 5/8"	11 5/8"	2 1/4"	5 5/8"	5/8"	3"	5/8"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3 9/32"	7/16"	2 3/16"	7/16"
KING	2 5/8"	9 5/8"	2 5/8"	5 9/32"	7/16"	2 3/16"	7/16"
ESTATE	2 5/8"	9 5/8"	3 5/8"	5 9/32"	7/16"	2 3/16"	7/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	1 5/8"	5/8"	3"	5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	5 5/8"	5/8"	3"	5/8"

Bullnose Flat Wall Cap Diagram




TOP VIEW

FRONT VIEW



SIDE VIEW



RWC-08-1

RWC-08-2

ISO VIEW




Rowlock Wall Caps - Bullnose Flat


Table of Contents

Wall Cap Gallery


Other Bullnose Flat Wall Cap Options



TOP VIEW




FRONT VIEW




SIDE VIEW


profile only
on one side




ISO VIEW




RWT-08-1
Watertable Bullnose
Flat Rowlock



TOP VIEW




FRONT VIEW




SIDE VIEW


profile on both
sides with joint
on top




ISO VIEW




*Field Cut
RWT-08-1
Watertable Bullnose
Flat Rowlock




RWC-08-2 Bullnose
Flat Wall Cap
End



TOP VIEW




FRONT VIEW




SIDE VIEW


profile on
both sides
for wider walls




ISO VIEW



RWT-08-1
Watertable Bullnose
Flat Rowlock



*Field Cut
RWT-08-1
Watertable Bullnose
Flat Rowlock



*Field Cut
RWC-08-2 Bullnose
Flat Wall Cap
End




Rowlock Wall Caps - Full Bullnose

Table of Contents

Wall Cap Gallery



RWC-09-1 Wall Cap




RWC-09-1	ROWLOCK WALL CAP - FULL BULLNOSE					
	A	B	C	D	E	F
MODULAR	3 5/8"	10 21/32"	2 1/4"	7 5/8"	5/8"	1 1/2"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8 19/32"	5/8"	1 1/2"
QUEEN	2 5/8"	9 13/16"	2 5/8"	7 5/8"	7/16"	1 3/32"
KING	2 5/8"	11 5/8"	2 5/8"	9 7/16"	7/16"	1 3/32"
ESTATE	2 5/8"	11 5/8"	3 5/8"	9 7/16"	7/16"	1 3/32"
CLOSURE	3 5/8"	10 21/32"	3 5/8"	7 5/8"	5/8"	1 1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 19/32"	5/8"	1 1/2"

RWC-09-2 End

RWC-09-2	ROWLOCK WALL CAP - FULL BULLNOSE - END							
	A	B	C	D	E	F	G	H
MODULAR	3 5/8"	10 21/32"	3 5/8"	7 5/8"	5/8"	1 1/2"	5 1/8"	3 5/8"
NORMAN	3 5/8"	11 5/8"	3 5/8"	8 19/32"	5/8"	1 1/2"	5 1/8"	3 5/8"
QUEEN	2 5/8"	9 13/16"	3 5/8"	7 5/8"	7/16"	1 3/32"	4 23/32"	3 5/8"
KING	2 5/8"	11 5/8"	3 5/8"	9 7/16"	7/16"	1 3/32"	4 23/32"	3 5/8"
ESTATE	2 5/8"	11 5/8"	3 5/8"	9 7/16"	7/16"	1 3/32"	4 23/32"	3 5/8"
CLOSURE	3 5/8"	10 21/32"	3 5/8"	7 5/8"	5/8"	1 1/2"	5 1/8"	3 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8 19/32"	5/8"	1 1/2"	5 1/8"	3 5/8"



Full Bullnose Wall Cap Diagram














Rowlock Wall Caps - Full Bullnose

Table of Contents

Wall Cap Gallery

Other Full Bullnose Wall Cap Options






Rowlock Wall Caps - Coping

Table of Contents


Wall Cap Gallery

RWC-10-1 Wall Cap





RWC-10-1	ROWLOCK WALL CAP - COPING				
	A	B	C	D	E
MODULAR	3 5/8"	11 5/8"	2 1/4"	8"	1 13/16"
NORMAN	3 5/8"	11 5/8"	2 1/4"	8"	1 13/16"
QUEEN	2 5/8"	11 5/8"	2 5/8"	9"	1 5/16"
KING	2 5/8"	11 5/8"	2 5/8"	9"	1 5/16"
ESTATE	2 5/8"	11 5/8"	3 5/8"	9"	1 5/16"
CLOSURE	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"

RWC-10-2 End



RWC-10-2	ROWLOCK WALL CAP - COPING - END					
	A	B	C	D	E	F
MODULAR	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"	5 7/16"
NORMAN	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"	5 7/16"
QUEEN	2 5/8"	11 5/8"	3 5/8"	9"	1 5/16"	4 15/16"
KING	2 5/8"	11 5/8"	3 5/8"	9"	1 5/16"	4 15/16"
ESTATE	2 5/8"	11 5/8"	3 5/8"	9"	1 5/16"	4 15/16"
CLOSURE	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"	5 7/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	8"	1 13/16"	5 7/16"

Sloped Wall Cap Diagram





Rowlock Wall Caps - Coping

Table of Contents

Wall Cap Gallery

Other Sloped Wall Cap Options














Table of Contents

Click on any shape for more details.

Soldiers




























SLOPED			
	SDR-01-1 Soldier - Sloped	SDR-01-2 Soldier - Sloped - Outside Corner	SDR-01-3 Soldier - Sloped - Inside Corner
BULLNOSE			
	SDR-02-1 Soldier - Bullnose	SDR-02-2 Soldier - Bullnose - Outside Corner	SDR-02-3 Soldier - Bullnose - Inside Corner
COVE			
	SDR-03-1 Soldier - Cove	SDR-03-2 Soldier - Cove - Outside Corner	SDR-03-3 Soldier - Cove - Inside Corner
OGEE			
	SDR-04-1 Soldier - Ogee	SDR-04-2 Soldier - Ogee - Outside Corner	SDR-04-3 Soldier - Ogee - Inside Corner
BULLNOSE OGEE			
	SDR-05-1 Soldier - Bullnose Ogee	SDR-05-2 Soldier - Bullnose Ogee - Outside Corner	SDR-05-3 Soldier - Bullnose Ogee - Inside Corner

Table of Contents

Click on any shape for more details.

Soldiers

COVE OGEE			
	SDR-06-1 Soldier - Cove Ogee	SDR-06-2 Soldier - Cove Ogee - Outside Corner	SDR-06-3 Soldier - Cove Ogee - Inside Corner
CROWN OGEE			
	SDR-07-1 Soldier - Crown Ogee	SDR-07-2 Soldier - Crown Ogee - Outside Corner	SDR-07-3 Soldier - Crown Ogee - Inside Corner
BULLNOSE FLAT			
	SDR-08-1 Soldier - Bullnose Flat	SDR-08-2 Soldier - Bullnose Flat - Outside Corner	SDR-08-3 Soldier - Bullnose Flat - Inside Corner
FULL BULLNOSE			
	SDR-09-1 Soldier - Full Bullnose	SDR-09-2 Soldier - Full Bullnose - Outside Corner	SDR-09-3 Soldier - Full Bullnose - Inside Corner
COPING	SDR-09 Full Bullnose soldiers can be used to match Profile 10 Coping shapes.		




Soldiers - Sloped

Table of Contents


Soldier Gallery

SDR-01-1 Soldier




SDR-01-1	SOLDIER - SLOPED				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	2 1/4"	5 1/4"	1 1/4"
NORMAN	11 5/8"	3 5/8"	2 1/4"	9 1/4"	1 1/4"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5 13/16"	13/16"
KING	9 5/8"	2 5/8"	2 5/8"	7 13/16"	13/16"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7 13/16"	13/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 1/4"	1 1/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 1/4"	1 1/4"

SDR-01-2 Outside Corner



SDR-01-2	SOLDIER - SLOPED - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 1/4"	1 1/4"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 1/4"	1 1/4"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 13/16"	1 13/16"
KING	9 5/8"	3 5/8"	3 5/8"	7 13/16"	1 13/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 13/16"	1 13/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 1/4"	1 1/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 1/4"	1 1/4"

SDR-01-3 Inside Corner



SDR-01-3	SOLDIER - SLOPED - INSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 1/4"	1 1/4"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 1/4"	1 1/4"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 13/16"	1 13/16"
KING	9 5/8"	3 5/8"	3 5/8"	7 13/16"	1 13/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 13/16"	1 13/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 1/4"	1 1/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 1/4"	1 1/4"




Soldiers - Sloped


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW




Soldiers - Bullnose

Table of Contents


Soldier Gallery

SDR-02-1 Soldier




SDR-02-1	SOLDIER - BULLNOSE				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	2 1/4"	4 13/32"	3 7/32"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8 13/32"	3 7/32"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5 1/4"	2 3/8"
KING	9 5/8"	2 5/8"	2 5/8"	7 1/4"	2 3/8"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7 1/4"	2 3/8"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 13/32"	3 7/32"

SDR-02-2 Outside Corner



SDR-02-2	SOLDIER - BULLNOSE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	4 13/32"	3 7/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8 13/32"	3 7/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 1/4"	2 3/8"
KING	9 5/8"	3 5/8"	3 5/8"	7 1/4"	2 3/8"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 1/4"	2 3/8"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 13/32"	3 7/32"

SDR-02-3 Inside Corner



SDR-02-3	SOLDIER - BULLNOSE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	4 13/32"	3 7/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8 13/32"	3 7/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 1/4"	2 3/8"
KING	9 5/8"	3 5/8"	3 5/8"	7 1/4"	2 3/8"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 1/4"	2 3/8"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 13/32"	3 7/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 13/32"	3 7/32"






Soldiers - Bullnose


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW




Soldiers - Cove

Table of Contents


Soldier Gallery

SDR-03-1 Soldier




SDR-03-1	SOLDIER - COVE					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	2 1/4"	5 7/32"	1 7/32"	2 13/32"
NORMAN	11 5/8"	3 5/8"	2 1/4"	9 7/32"	1 7/32"	2 13/32"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5 7/8"	7/8"	1 3/4"
KING	9 5/8"	2 5/8"	2 5/8"	7 7/8"	7/8"	1 3/4"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7 7/8"	7/8"	1 3/4"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"

SDR-03-2 Outside Corner



SDR-03-2	SOLDIER - COVE - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 7/8"	1 7/8"	1 3/4"
KING	9 5/8"	3 5/8"	3 5/8"	7 7/8"	1 7/8"	1 3/4"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 7/8"	1 7/8"	1 3/4"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"

SDR-03-3 Inside Corner



SDR-03-3	SOLDIER - COVE - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 7/8"	1 7/8"	1 3/4"
KING	9 5/8"	3 5/8"	3 5/8"	7 7/8"	1 7/8"	1 3/4"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 7/8"	1 7/8"	1 3/4"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 7/32"	1 7/32"	2 13/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 7/32"	1 7/32"	2 13/32"




Soldiers - Cove


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW




ISO VIEW

Soldiers - Ogee

Table of Contents


Soldier Gallery

SDR-04-1 Soldier




SDR-04-1	SOLDIER - OGEE				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	2 1/4"	5 3/8"	2"
NORMAN	11 5/8"	3 5/8"	2 1/4"	9 3/8"	2"
QUEEN	7 5/8"	2 5/8"	2 5/8"	6"	1 7/16"
KING	9 5/8"	2 5/8"	2 5/8"	8"	1 7/16"
ESTATE	9 5/8"	2 5/8"	3 5/8"	8"	1 7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 3/8"	2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 3/8"	2"

SDR-04-2 Outside Corner



SDR-04-2	SOLDIER - OGEE - OUTSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 3/8"	2"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 3/8"	2"
QUEEN	7 5/8"	3 5/8"	3 5/8"	6"	1 7/16"
KING	9 5/8"	3 5/8"	3 5/8"	8"	1 7/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	8"	1 7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 3/8"	2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 3/8"	2"

SDR-04-3 Inside Corner




SDR-04-3	SOLDIER - OGEE - INSIDE CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	3 5/8"	5 3/8"	2"
NORMAN	11 5/8"	3 5/8"	3 5/8"	9 3/8"	2"
QUEEN	7 5/8"	3 5/8"	3 5/8"	6"	1 7/16"
KING	9 5/8"	3 5/8"	3 5/8"	8"	1 7/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	8"	1 7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	5 3/8"	2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	9 3/8"	2"

Soldiers - Ogee


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW




ISO VIEW

Soldiers - Bullnose Ogee

Table of Contents


Soldier Gallery

SDR-05-1 Soldier




SDR-05-1	SOLDIER - BULLNOSE OGEE						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	2 1/4"	4"	1 1/8"	3"	2 21/32"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8"	1 1/8"	3"	2 21/32"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5"	13/16"	2 3/16"	1 15/16"
KING	9 5/8"	2 5/8"	2 5/8"	7"	13/16"	2 3/16"	1 15/16"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7"	13/16"	2 3/16"	1 15/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	1 1/8"	3"	2 21/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	1 1/8"	3"	2 21/32"

SDR-05-2 Outside Corner



SDR-05-2	SOLDIER - BULLNOSE OGEE - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	1 1/8"	3"	2 21/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	1 1/8"	3"	2 21/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	13/16"	2 3/16"	2 15/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	13/16"	2 3/16"	2 15/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	13/16"	2 3/16"	2 15/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	1 1/8"	3"	2 21/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	1 1/8"	3"	2 21/32"

SDR-05-3 Inside Corner




SDR-05-3	SOLDIER - BULLNOSE OGEE - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	1 1/8"	3"	2 21/32"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	1 1/8"	3"	2 21/32"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	13/16"	2 3/16"	2 15/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	13/16"	2 3/16"	2 15/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	13/16"	2 3/16"	2 15/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	1 1/8"	3"	2 21/32"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	1 1/8"	3"	2 21/32"

Soldiers - Bullnose Ogee


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW




Soldiers - Cove Ogee

Table of Contents


Soldier Gallery

SDR-06-1 Soldier




SDR-06-1	SOLDIER - COVE OGEE							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	2 1/4"	4"	3/4"	1 5/16"	1 9/16"	3/4"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8"	3/4"	1 5/16"	1 9/16"	3/4"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5"	9/16"	15/16"	1 1/8"	9/16"
KING	9 5/8"	2 5/8"	2 5/8"	7"	9/16"	15/16"	1 1/8"	9/16"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7"	9/16"	15/16"	1 1/8"	9/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	3/4"	1 5/16"	1 9/16"	3/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	3/4"	1 5/16"	1 9/16"	3/4"

SDR-06-2 Outside Corner



SDR-06-2	SOLDIER - COVE OGEE - OUTSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	3/4"	1 5/16"	1 9/16"	3/4"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	3/4"	1 5/16"	1 9/16"	3/4"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	9/16"	15/16"	1 1/8"	1 9/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	9/16"	15/16"	1 1/8"	1 9/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	9/16"	15/16"	1 1/8"	1 9/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	3/4"	1 5/16"	1 9/16"	3/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	3/4"	1 5/16"	1 9/16"	3/4"

SDR-06-3 Inside Corner



SDR-06-3	SOLDIER - COVE OGEE - INSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	3/4"	1 5/16"	1 9/16"	3/4"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	3/4"	1 5/16"	1 9/16"	3/4"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	9/16"	15/16"	1 1/8"	1 9/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	9/16"	15/16"	1 1/8"	1 9/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	9/16"	15/16"	1 1/8"	1 9/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	3/4"	1 5/16"	1 9/16"	3/4"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	3/4"	1 5/16"	1 9/16"	3/4"




Soldiers - Cove Ogee


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW




ISO VIEW

Soldiers - Crown Ogee

Table of Contents


Soldier Gallery

SDR-07-1 Soldier




SDR-07-1	SOLDIER - CROWN OGEE							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	2 1/4"	4"	9/16"	15/16"	1 1/2"	1 5/8"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8"	9/16"	15/16"	1 1/2"	1 5/8"
QUEEN	7 5/8"	3 5/8"	2 5/8"	5"	13/32"	11/16"	1 3/32"	2 3/16"
KING	9 5/8"	3 5/8"	2 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	9/16"	15/16"	1 1/2"	1 5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	9/16"	15/16"	1 1/2"	1 5/8"

SDR-07-2 Outside Corner



SDR-07-2	SOLDIER - CROWN OGEE - OUTSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	9/16"	15/16"	1 1/2"	1 5/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	9/16"	15/16"	1 1/2"	1 5/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	13/32"	11/16"	1 3/32"	2 3/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	9/16"	15/16"	1 1/2"	1 5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	9/16"	15/16"	1 1/2"	1 5/8"

SDR-07-3 Inside Corner




SDR-07-3	SOLDIER - CROWN OGEE - INSIDE CORNER							
	A	B	C	D	E	F	G	H
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	9/16"	15/16"	1 1/2"	1 5/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	9/16"	15/16"	1 1/2"	1 5/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	13/32"	11/16"	1 3/32"	2 3/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	13/32"	11/16"	1 3/32"	2 3/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	9/16"	15/16"	1 1/2"	1 5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	9/16"	15/16"	1 1/2"	1 5/8"

Soldiers - Crown Ogee


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW




Soldiers - Bullnose Flat

Table of Contents


Soldier Gallery

SDR-08-1 Soldier




SDR-08-1	SOLDIER - BULLNOSE FLAT						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	2 1/4"	4"	5/8"	3"	5/8"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8"	5/8"	3"	5/8"
QUEEN	7 5/8"	2 5/8"	2 5/8"	5"	7/16"	2 3/16"	7/16"
KING	9 5/8"	2 5/8"	2 5/8"	7"	7/16"	2 3/16"	7/16"
ESTATE	9 5/8"	2 5/8"	3 5/8"	7"	7/16"	2 3/16"	7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	5/8"	3"	5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	5/8"	3"	5/8"

SDR-08-2 Outside Corner



SDR-08-2	SOLDIER - BULLNOSE FLAT - OUTSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	5/8"	3"	5/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	5/8"	3"	5/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	7/16"	2 3/16"	1 7/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	7/16"	2 3/16"	1 7/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	7/16"	2 3/16"	1 7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	5/8"	3"	5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	5/8"	3"	5/8"

SDR-08-3 Inside Corner



SDR-08-3	SOLDIER - BULLNOSE FLAT - INSIDE CORNER						
	A	B	C	D	E	F	G
MODULAR	7 5/8"	3 5/8"	3 5/8"	4"	5/8"	3"	5/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8"	5/8"	3"	5/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5"	7/16"	2 3/16"	1 7/16"
KING	9 5/8"	3 5/8"	3 5/8"	7"	7/16"	2 3/16"	1 7/16"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7"	7/16"	2 3/16"	1 7/16"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4"	5/8"	3"	5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8"	5/8"	3"	5/8"




Soldiers - Bullnose Flat


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW




Soldiers - Full Bullnose

Table of Contents


Soldier Gallery

SDR-09-1 Soldier




SDR-09-1	SOLDIER - FULL BULLNOSE					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	2 1/4"	4 5/8"	1 1/2"	2 1/8"
NORMAN	11 5/8"	3 5/8"	2 1/4"	8 5/8"	1 1/2"	2 1/8"
QUEEN	7 5/8"	3 5/8"	2 5/8"	5 7/16"	1 3/32"	2 17/32"
KING	9 5/8"	3 5/8"	2 5/8"	5 7/16"	1 3/32"	2 17/32"
ESTATE	9 5/8"	3 5/8"	3 5/8"	5 7/16"	1 3/32"	2 17/32"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 5/8"	1 1/2"	2 1/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 5/8"	1 1/2"	2 1/8"

SDR-09-2 Outside Corner



SDR-09-2	SOLDIER - FULL BULLNOSE - OUTSIDE CORNER					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	3 5/8"	4 5/8"	1 1/2"	2 1/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8 5/8"	1 1/2"	2 1/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 7/16"	1 3/32"	2 17/32"
KING	9 5/8"	3 5/8"	3 5/8"	7 7/16"	1 3/32"	2 17/32"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 7/16"	1 3/32"	2 17/32"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 5/8"	1 1/2"	2 1/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 5/8"	1 1/2"	2 1/8"

SDR-09-3 Inside Corner



SDR-09-3	SOLDIER - FULL BULLNOSE - INSIDE CORNER					
	A	B	C	D	E	F
MODULAR	7 5/8"	3 5/8"	3 5/8"	4 5/8"	1 1/2"	2 1/8"
NORMAN	11 5/8"	3 5/8"	3 5/8"	8 5/8"	1 1/2"	2 1/8"
QUEEN	7 5/8"	3 5/8"	3 5/8"	5 7/16"	1 3/32"	2 17/32"
KING	9 5/8"	3 5/8"	3 5/8"	7 7/16"	1 3/32"	2 17/32"
ESTATE	9 5/8"	3 5/8"	3 5/8"	7 7/16"	1 3/32"	2 17/32"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	4 5/8"	1 1/2"	2 1/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"	8 5/8"	1 1/2"	2 1/8"




Soldiers - Full Bullnose


Table of Contents

Soldier Gallery


Soldier Course Diagram



TOP VIEW



FRONT VIEW



ISO VIEW


Copings

Table of Contents


Rowlock and watertable shapes are identical to the shapes sometimes referred to as "pool coping". Rather than list these shapes again with different ordering numbers, we instead present diagrams here, as examples of how to shapes in these applications. Simply order more of the desired shape for any coping use.

Coping Diagrams


*Corner treatment as desired



TOP VIEW




ISO VIEW




FWT-10-1
Flat Watertable
Coping


*Corner treatment as desired



TOP VIEW



ISO VIEW




FWT-09-1
Flat Watertable
Full Bullnose


Copings

Table of Contents

*Corner treatment as desired



TOP VIEW




ISO VIEW

*Field Cut




RWT-02-1
Rowlock Bullnose


*Corner treatment as desired



TOP VIEW



ISO VIEW




RWT-05-1
Rowlock
Bullnose Ogee

Treads


Table of Contents

Watertable shapes are identical to the shapes classified as stair treads. Rather than list these shapes again with different ordering numbers, we instead present diagrams of how to use the watertable shapes as treads. Simply order more of the desired watertable shape for any tread use. Please note that building codes may require certain parameters for stairs. Be sure to follow all local codes.


Tread Diagrams



TOP VIEW




ISO VIEW




RWT-05-1
Rowlock Watertable
Bullnose Ogee




RWT-05-2
Rowlock Watertable
Bullnose Ogee
Outside Corner



TOP VIEW



ISO VIEW




RWT-09-1
Rowlock Watertable
Full Bullnose




RWT-09-2
Rowlock Watertable
Full Bullnose
Outside Corner

Treads


Table of Contents



TOP VIEW



ISO VIEW




FWT-09-1
Flat Watertable
Full Bullnose




FWT-09-2
Flat Watertable Full
Bullnose Outside
Corner


*To extend the length of treads, FWT-09-1 pieces can be cut to size, or field brick may be used.




TOP VIEW



ISO VIEW



FWT-10-1
Flat Watertable
Coping



FWT-10-4
Flat Watertable
Coping Stretcher



FWT-10-2
Flat Watertable
Coping Outside
Corner

Example Wall Diagram



Table of Contents

Same Profile

Here is an example of what it looks like when when you use a single profile across multiple shape types, in this case Profile **09 Full Bullnose**.



not used



Example Wall Diagram

Table of Contents

Different Profiles

Here is an example of what it looks like when when you use multiple profiles and shapes, in this case Profiles:



01 Sloped



03 Cove



05 Bullnose Ogee




07 Crown Ogee



08 Bullnose Flat




10 Coping




Click on any shape for more details.

Corners - External Short


Corners




CNR-01-1 Corner - External Short




CNR-01-2 Corner - External Long




CNR-01-3 Corner - Internal




CNR-01-4 Corner - Hinge Brick



CNR-02-1 Corner - Soldier



CNR-02-2 Corner - External Soldier



CNR-02-3 Corner - Internal Soldier


external corners



hinge brick as 90° corner




CNR-01-1 Corner - External Short




CNR-01-1	CORNER - EXTERNAL SHORT					
	A	B	C	D	E	F
MODULAR	2 1/4"	Varies	3 5/8"	6"	2"	Degree of Corner
NORMAN	2 1/4"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner
QUEEN	2 5/8"	Varies	2 5/8"	6"	2"	Degree of Corner
KING	2 5/8"	Varies	2 5/8"	5 7/8"	2 3/4"	Degree of Corner
ESTATE	3 5/8"	Varies	2 5/8"	5 7/8"	2 3/4"	Degree of Corner
CLOSURE	3 5/8"	Varies	3 5/8"	6"	2"	Degree of Corner
UTILITY	3 5/8"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner


If the Dimension "B" is over 11 5/8" then the two leg Dimension "D" & "E" will have to be shortened. Dimension "F" is rounded to the nearest whole degree.



TOP VIEW



FRONT VIEW



ISO VIEW

Piece are flipped over to create the corner.




CNR-01-1

Corners - External Long

Table of Contents


Corner Gallery

CNR-01-2 Corner - External Long




CNR-01-2	CORNER - EXTERNAL LONG					
	A	B	C	D	E	F
MODULAR	2 1/4"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner
NORMAN	2 1/4"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner
QUEEN	2 5/8"	Varies	2 5/8"	6 3/4"	2 3/4"	Degree of Corner
KING	2 5/8"	Varies	2 5/8"	9 5/8"	2 3/4"	Degree of Corner
ESTATE	3 5/8"	Varies	2 5/8"	9 5/8"	2 3/4"	Degree of Corner
CLOSURE	3 5/8"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner
UTILITY	3 5/8"	Varies	3 5/8"	7 5/8"	3 5/8"	Degree of Corner


If the Dimension "B" is over 11 5/8" then the two leg Dimension "D" & "E" will have to be shortened. Dimension "F" is rounded to the nearest whole degree.



TOP VIEW



FRONT VIEW



ISO VIEW

Piece are flipped over to create the corner.


CNR-01-2

Corners - Internal

Table of Contents


Corner Gallery

CNR-01-3 Corner - Internal




CNR-01-3	CORNER - INTERNAL					
	A	B	C	D	E	F
MODULAR	2 1/4"	Varies	3 5/8"	6"	2"	Degree of Corner
NORMAN	2 1/4"	Varies	3 5/8"	6"	2"	Degree of Corner
QUEEN	2 5/8"	Varies	2 5/8"	6"	2"	Degree of Corner
KING	2 5/8"	Varies	2 5/8"	5 7/8"	2 3/4"	Degree of Corner
ESTATE	3 5/8"	Varies	2 5/8"	5 7/8"	2 3/4"	Degree of Corner
CLOSURE	3 5/8"	Varies	3 5/8"	6"	2"	Degree of Corner
UTILITY	3 5/8"	Varies	3 5/8"	6"	2"	Degree of Corner


If the Dimension "B" is over 11 5/8" then the two leg Dimension "D" & "E" will have to be shortened. Dimension "F" is rounded to the nearest whole degree.



TOP VIEW



FRONT VIEW



ISO VIEW

Piece are flipped over to create the corner.


CNR-01-3

Corners - Hinge Brick

Table of Contents


Corner Gallery

CNR-01-4 Corner - Hinge Brick




CNR-01-4	CORNERS - HINGE BRICK					
	A	B	C	D	E	F
MODULAR	2 1/4"	7 5/8"	3 5/8"	3 5/8"	3 5/8"	1 13/16"
NORMAN	2 1/4"	11 5/8"	3 5/8"	7 5/8"	3 5/8"	1 13/16"
QUEEN	2 5/8"	6 5/8"	2 5/8"	3 5/8"	2 5/8"	1 5/16"
KING	2 5/8"	9 1/2"	2 5/8"	6 1/2"	2 5/8"	1 5/16"
ESTATE	3 5/8"	9 1/2"	2 5/8"	6 1/2"	2 5/8"	1 5/16"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3 5/8"	3 5/8"	1 13/16"
UTILITY	3 5/8"	11 5/8"	3 5/8"	7 5/8"	3 5/8"	1 13/16"

Hinge brick is a single shape that can be laid at any angle, here shown at 135 or 120 degrees.




TOP VIEW




FRONT VIEW

Pieces are flipped over to create the corner.



CNR-01-4



ISO VIEW


Corners - Hinge Brick

Table of Contents


Corner Gallery

Other Hinge Brick Diagrams


Hinge brick can be laid at any angle, here shown at 90 degrees.



TOP VIEW




FRONT VIEW




ISO VIEW


Hinge brick can be laid as window jambs.




TOP VIEW



FRONT VIEW



ISO VIEW




CNR-01-4

Corners - Soldiers

Table of Contents


Corner Gallery

CNR-02-1 Corner - Soldier



CNR-02-1	CORNERS - SOLDIER		
	A	B	C
MODULAR	7 5/8"	2 1/4"	2 1/4"
NORMAN	11 5/8"	2 1/4"	2 1/4"
QUEEN	7 5/8"	2 5/8"	2 5/8"
KING	9 5/8"	2 5/8"	2 5/8"
ESTATE	9 5/8"	3 5/8"	3 5/8"
CLOSURE	7 5/8"	3 5/8"	3 5/8"
UTILITY	11 5/8"	3 5/8"	3 5/8"


CNR-02-2 Corner - External Soldier



CNR-02-2	CORNERS - EXTERNAL SOLDIER				
	A	B	C	D	E
MODULAR	7 5/8"	3 5/8"	Varies	2 1/4"	Degree of Corner
NORMAN	11 5/8"	3 5/8"	Varies	2 1/4"	Degree of Corner
QUEEN	7 5/8"	2 5/8"	Varies	2 5/8"	Degree of Corner
KING	9 5/8"	2 5/8"	Varies	2 5/8"	Degree of Corner
ESTATE	9 5/8"	2 5/8"	Varies	3 5/8"	Degree of Corner
CLOSURE	7 5/8"	3 5/8"	Varies	3 5/8"	Degree of Corner
UTILITY	11 5/8"	3 5/8"	Varies	3 5/8"	Degree of Corner

Dimension "E" is rounded to the nearest whole degree.

CNR-02-3 Corner - Internal Soldier



CNR-02-3	CORNERS - INTERNAL SOLDIER				
	A	B	C	D	E
MODULAR	7 5/8"	2 1/4"	3 5/8"	Varies	Degree of Corner
NORMAN	11 5/8"	2 1/4"	3 5/8"	Varies	Degree of Corner
QUEEN	7 5/8"	2 5/8"	2 5/8"	Varies	Degree of Corner
KING	9 5/8"	2 5/8"	2 5/8"	Varies	Degree of Corner
ESTATE	9 5/8"	3 5/8"	2 5/8"	Varies	Degree of Corner
CLOSURE	7 5/8"	3 5/8"	3 5/8"	Varies	Degree of Corner
UTILITY	11 5/8"	3 5/8"	3 5/8"	Varies	Degree of Corner


Dimension "E" is rounded to the nearest whole degree.

Corners - Soldiers


Table of Contents

Corner Gallery

Soldier Corner Diagrams




TOP VIEW




FRONT VIEW


Two corner options shown here. On the left it is one corner shape with two field cut face brick. On the right three corners shapes are used with no field cuts needed.




ISO VIEW




CNR-02-1




TOP VIEW




FRONT VIEW



ISO VIEW



CNR-02-2



CNR-02-3

Table of Contents


Click on any shape for more details.

Shelf Angles


Table of Contents

Shelf Angle Gallery


Shelf Angles




SHA-01-1 Shelf Angle - Stretcher




SHA-01-2 Shelf Angle - Stretcher - Corner Left




SHA-01-3 Shelf Angle - Stretcher - Corner Right




SHA-02-1 Shelf Angle - Soldier



SHA-02-2 Shelf Angle - Soldier - Corner




SHA-03-1 Shelf Angle - Rowlock




SHA-03-2 Shelf Angle - Rowlock - Corner

indicates bottom of shape


Radial Brick




RAD-01-1 Outside Radial Stretcher




RAD-01-2 Outside Radial Starter



RAD-02-1 Inside Radial Stretcher




RAD-02-2 Inside Radial Starter




radial brick columns

SHA-01-1 Shelf Angle - Stretcher




SHA-01-1	SHELF ANGLE - STRETCHER				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	3/4"	1/2"
NORMAN	2 1/4"	11 5/8"	3 5/8"	3/4"	1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3/4"	1/2"
KING	2 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
ESTATE	3 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3/4"	1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	3/4"	1/2"

SHA-01-2 Shelf Angle - Stretcher - Corner Left



SHA-01-2	SHELF ANGLE - STRETCHER - CORNER LEFT				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	3/4"	1/2"
NORMAN	2 1/4"	11 5/8"	3 5/8"	3/4"	1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3/4"	1/2"
KING	2 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
ESTATE	3 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3/4"	1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	3/4"	1/2"

SHA-01-3 Shelf Angle - Stretcher - Corner Right



SHA-01-3	SHELF ANGLE - STRETCHER - CORNER RIGHT				
	A	B	C	D	E
MODULAR	2 1/4"	7 5/8"	3 5/8"	3/4"	1/2"
NORMAN	2 1/4"	11 5/8"	3 5/8"	3/4"	1/2"
QUEEN	2 5/8"	7 5/8"	2 5/8"	3/4"	1/2"
KING	2 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
ESTATE	3 5/8"	9 5/8"	2 5/8"	3/4"	1/2"
CLOSURE	3 5/8"	7 5/8"	3 5/8"	3/4"	1/2"
UTILITY	3 5/8"	11 5/8"	3 5/8"	3/4"	1/2"


** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Shelf Angles

Table of Contents


Shelf Angle Gallery

SHA-02-1 Shelf Angle - Soldier




SHA-02-1	SHELF ANGLE - SOLDIER				
	A	B	C	D	E
MODULAR	7 5/8"	2 1/4"	3 5/8"	3/4"	1/2"
NORMAN	11 5/8"	2 1/4"	3 5/8"	3/4"	1/2"
QUEEN	7 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
KING	9 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
ESTATE	9 5/8"	3 5/8"	2 5/8"	3/4"	1/2"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	3/4"	1/2"

SHA-02-2 Shelf Angle - Soldier - Corner




SHA-02-2	SHELF ANGLE - SOLDIER - CORNER				
	A	B	C	D	E
MODULAR	7 5/8"	2 1/4"	2 1/4"	3/4"	1/2"
NORMAN	11 5/8"	2 1/4"	2 1/4"	3/4"	1/2"
QUEEN	7 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
KING	9 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
ESTATE	9 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	3/4"	1/2"

SHA-03-1 Shelf Angle - Rowlock



SHA-03-1	SHELF ANGLE - ROWLOCK				
	A	B	C	D	E
MODULAR	7 5/8"	2 1/4"	3 5/8"	3/4"	1/2"
NORMAN	11 5/8"	2 1/4"	3 5/8"	3/4"	1/2"
QUEEN	7 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
KING	9 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
ESTATE	9 5/8"	3 5/8"	2 5/8"	3/4"	1/2"
CLOSURE	7 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
UTILITY	11 5/8"	3 5/8"	3 5/8"	3/4"	1/2"

SHA-03-2 Shelf Angle - Rowlock - Corner




SHA-03-2	SHELF ANGLE - ROWLOCK - CORNER				
	A	B	C	D	E
MODULAR	3 5/8"	2 1/4"	2 1/4"	3/4"	1/2"
NORMAN	3 5/8"	2 1/4"	2 1/4"	3/4"	1/2"
QUEEN	2 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
KING	2 5/8"	2 5/8"	2 5/8"	3/4"	1/2"
ESTATE	2 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
CLOSURE	3 5/8"	3 5/8"	3 5/8"	3/4"	1/2"
UTILITY	3 5/8"	3 5/8"	3 5/8"	3/4"	1/2"

Shelf Angles


Table of Contents

Shelf Angle Gallery


Shelf Angle Diagram



TOP VIEW



FRONT VIEW




Radial Brick

Table of Contents


Radial Gallery

RAD-01-1 Radial Outside Stretcher



RAD-01-1	RADIAL OUTSIDE STRETCHER			
	A	B	C	D
MODULAR	2 1/4"	~7 5/8"	3 5/8"	Radius
NORMAN	2 1/4"	~11 5/8"	3 5/8"	Radius
QUEEN	2 5/8"	~7 5/8"	2 5/8"	Radius
KING	2 5/8"	~9 5/8"	2 5/8"	Radius
ESTATE	3 5/8"	~9 5/8"	2 5/8"	Radius
CLOSURE	3 5/8"	~7 5/8"	3 5/8"	Radius
UTILITY	3 5/8"	~11 5/8"	3 5/8"	Radius

RAD-01-2 Radial Outside Starter



RAD-01-2	RADIAL OUTSIDE STARTER			
	A	B	C	D
MODULAR	2 1/4"	~7 5/8"	3 5/8"	Radius
NORMAN	2 1/4"	~11 5/8"	3 5/8"	Radius
QUEEN	2 5/8"	~7 5/8"	2 5/8"	Radius
KING	2 5/8"	~9 5/8"	2 5/8"	Radius
ESTATE	3 5/8"	~9 5/8"	2 5/8"	Radius
CLOSURE	3 5/8"	~7 5/8"	3 5/8"	Radius
UTILITY	3 5/8"	~11 5/8"	3 5/8"	Radius

Please note: For curved walls, if the radius is less than below, a special shape radial brick is required.

If the radius is equal to or larger than dimensions below, a standard field brick may be used.

Modular Brick: Radius 8'0" or larger

King Size & Estate Size Brick: Radius 10'0" or larger





Utility & Norman Brick: Radius 12'0" or larger

Radial Brick





Table of Contents

Radial Gallery

Radial Outside Brick Diagrams



ISO VIEW



ISO VIEW


** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Radial Brick

Table of Contents


Radial Gallery

RAD-02-1 Radial Inside Stretcher



RAD-02-1	RADIAL INSIDE STRETCHER			
	A	B	C	D
MODULAR	2 1/4"	~7 5/8"	3 5/8"	Radius
NORMAN	2 1/4"	~11 5/8"	3 5/8"	Radius
QUEEN	2 5/8"	~7 5/8"	2 5/8"	Radius
KING	2 5/8"	~9 5/8"	2 5/8"	Radius
ESTATE	3 5/8"	~9 5/8"	2 5/8"	Radius
CLOSURE	3 5/8"	~7 5/8"	3 5/8"	Radius
UTILITY	3 5/8"	~11 5/8"	3 5/8"	Radius

RAD-02-2 Radial Inside Starter



RAD-02-2	RADIAL INSIDE STARTER			
	A	B	C	D
MODULAR	2 1/4"	~7 5/8"	3 5/8"	Radius
NORMAN	2 1/4"	~11 5/8"	3 5/8"	Radius
QUEEN	2 5/8"	~7 5/8"	2 5/8"	Radius
KING	2 5/8"	~9 5/8"	2 5/8"	Radius
ESTATE	3 5/8"	~9 5/8"	2 5/8"	Radius
CLOSURE	3 5/8"	~7 5/8"	3 5/8"	Radius
UTILITY	3 5/8"	~11 5/8"	3 5/8"	Radius

Please note: For curved walls, if the radius is less than below, a special shape radial brick is required.
If the radius is equal to or larger than dimensions below, a standard field brick may be used.


- Modular Brick: Radius 8'0" or larger
- King Size & Estate Size Brick: Radius 10'0" or larger
- Utility & Norman Brick: Radius 12'0" or larger

Radial Brick


Table of Contents

Radial Gallery



Inside Radial Brick Diagram



TOP VIEW



FRONT VIEW




ISO VIEW

Solids

Table of Contents


A solid brick shape can be finished out on any number of sides to suit various placement in a wall. Keep in mind that the finish, texture, and final wall placement of your order will change what kind of solid to order. Pieces are wire cut, which will match a Velour brick texture, but will need to be finished out on more sides for a texture like Bark or Ruff (see page 6 for images).

As these require more hand work, a minimum number must be ordered to warrant production. As with all shapes, ability to create them varies between plants, so be sure to ask your Acme Brick representative.




SLD	SOLID SHAPE		
	A	B	C
MODULAR	2 1/4"	7 5/8"	3 5/8"
NORMAN	2 1/4"	11 5/8"	3 5/8"
QUEEN	2 3/4"	7 5/8"	2 3/4"
KING	2 5/8"	9 5/8"	2 3/4"
ESTATE	3 5/8"	9 5/8"	2 3/4"
CLOSURE	3 5/8"	7 5/8"	3 5/8"
UTILITY	3 5/8"	11 5/8"	3 5/8"

Nomenclature note: SLD-0X-1, X is the number of finished faces.




SLD-03-1

Solid Three Faces Finished
Use SLD-03-1 if the texture on the Stretchers and Headers are Velour.




SLD-04-1

Solid Four Faces Finished
Use SLD-04-1 if the texture on the Stretchers and Headers are anything other than Velour.



SLD-05-1

Solid Five Faces Finished
Use SLD-05-1 if the texture on the Stretchers and Headers are anything other than Velour.



SLD-06-1




Solid Six Faces Finished
Use SLD-06-1 if the texture on the Stretchers and Headers are anything other than Velour.

Solids

Table of Contents

Three or Four Finished Faces Solid Brick Use Diagrams

For examples on this page, use **SLD-03-1** if the finished face texture is Velour, as it is similar to the wire cut side. Order **SLD-04-1** if the finished face is anything other than Velour, because one side will need to match the stretchers and headers.




** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.


Solids

Table of Contents

Three or Four Finished Faces Solid Brick Use Diagram



Five Finished Faces Solid Brick Use Diagram





lattice wall



Solids

Table of Contents

Six Finished Faces Solid Brick Use Diagrams



popped out brick





























Table of Contents

Click on any shape for more details.

Table of Contents

Click on any shape for more details.

Arches

	Jack Arch 3 Course	Jack Arch 4 Course	Jack Arch 5+ Course	Roman	Circular	Segmental	Elliptical	Jill Arch
One Piece	 ARC-01-1 Jack Arch 3 Course One Piece	 ARC-02-1 Jack Arch 4 Course One Piece	Jack Arches 5 courses and over are not feasible because a single piece over 11 5/8" cannot be produced.	 ARC-04-1 Roman Arch One Piece	 ARC-05-1 Circular Arch One Piece	 ARC-06-1 Segmental Arch One Piece	 ARC-07-1 Elliptical Arch One Piece	This arch type takes advantage of a single shape to create the arch and requires a keystone.
Note: The maximum manufacturing for pieces is 11 5/8" in length, restricting the size of one piece arches.								
Multi Piece	 ARC-01-2 Jack Arch 3 Course Multi Piece	 ARC-02-2 Jack Arch 4 Course Multi Piece	 ARC-03-2 Jack Arch 5+ Course Multi Piece	 ARC-04-2 Roman Arch Multi Piece	 ARC-05-2 Circular Arch Multi Piece	 ARC-06-2 Segmental Arch Multi Piece	 ARC-07-2 Elliptical Arch Multi Piece	This arch type takes advantage of a single shape to create the arch and requires a keystone.
One Piece w Key	 ARC-01-3 Jack Arch 3 Course One Piece with Keystone	 ARC-02-3 Jack Arch 4 Course One Piece with Keystone	Jack Arches with keystones, 5 courses and over are not feasible because a single piece over 11 5/8" cannot be produced.	 ARC-04-3 Roman Arch One Piece with Keystone	 ARC-05-3 Circular Arch One Piece with Keystone	 ARC-06-3 Segmental Arch One Piece with Keystone	 ARC-07-3 Elliptical Arch One Piece with Keystone	 ARC-08-3 Jill Arch One Piece with Keystone
Note: The maximum manufacturing for pieces is 11 5/8" in length, restricting the size of one piece arches.								
Multi Piece w Key	 ARC-01-4 Jack Arch 3 Course Multi Piece with Keystone	 ARC-02-4 Jack Arch 4 Course Multi Piece with Keystone	 ARC-03-4 Jack Arch 5+ Course Multi Piece with Keystone	 ARC-04-4 Roman Arch Multi Piece with Keystone	 ARC-05-4 Circular Arch Multi Piece with Keystone	 ARC-06-4 Segmental Arch Multi Piece with Keystone	 ARC-07-4 Elliptical Arch Multi Piece with Keystone	 ARC-08-4 Jill Arch Multi Piece with Keystone

Helpful Arch Information

When requesting an Approval Drawing for an Arch, please provide the information denoted as "ARCH DRAWING NOTATIONS" listed as variables A through K accordingly on each page for that type Arch. All Arches may or may not use all Notations, but they are the same throughout all arches.

The field brick size determines the bed depth of the Arch Pieces and they are typically cored.



All joints to be a consistent 3/8."

ARCH DRAWING NOTATIONS	
A	Arch Type
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces
E	Brick Size
F	Key Height
G	Key Top
H	Key Bottom
I	Radius 1
J	Rise
K	Radius 2

- "A" - **Arch Type** - pick the type of arch: Jack Arch, Roman, Circular, Segmental, Elliptical
- "B" - **Masonry Opening** - span of opening to be crossed, rounded down to the nearest 1/2 inch
- "C" - **Height of Arch** - The height of Jack Arches are given in number of courses. The height of Roman, Circular, Segmental and Elliptical arches can be given in number of courses or inches.
- "D" - **Number of Pieces** - When ordering Multi Piece Arches, you will need to specify the desired number of pieces the height of the arch is divided into. This decision is purely aesthetic. See examples below.
- "E" - **Brick Size** - width of field brick dictate the appropriate size, for Modular and Norman ~2 1/4", Queen and King ~2 5/8", Estate, Closure and Utility ~3 5/8"
- "F", "G", "H" - **Key Height, Top, or Bottom** - keystone dimensions
- "I" - **Radius 1** - radius of the arch
- "J" - **Rise** - the vertical distance from the spring line to the bottom of the Arch, in inches
- "K" - **Radius 2** - in Elliptical arches only, the second radius of the arch

Radial Arch Notes

For most Radial Arches (arches with an associated radius) the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening for radial arches gets larger, a field brick may be the best option, because the taper of the arch piece or the mortar joint is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.




3 Course Jack Arch

Table of Contents


Arch Gallery

ARC-01-1 Three Course Jack Arch One Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Three
D	Number of Pieces - One
E	Brick Size

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening and brick size chosen. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




Height of Arch	3 COURSE
MODULAR	7 1/2"
NORMAN	7 1/2"
QUEEN	9"
KING	9"
ESTATE	11 5/8"
CLOSURE	11 5/8"
UTILITY	11 5/8"

3 Course Jack Arch

Table of Contents


Arch Gallery

ARC-01-2 Three Course Jack Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Three
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening in inches and brick size chosen. The field brick size determines the bed depth of the Arch Pieces and they are typically cored. Example "D" number of pieces shown is 2P.




3 Course Jack Arch

Table of Contents

Arch Gallery

ARC-01-3 Three Course Jack Arch One Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Three
D	Number of Pieces - One
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom


Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen, as well as the dimensions of your chosen keystone. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.

3 Course Jack Arch

Table of Contents


Arch Gallery

ARC-01-4 Three Course Jack Arch Multi Piece with Keystone




ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Three
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen, as well as the dimensions of your chosen keystone. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.



Height of Arch	3 COURSE
MODULAR	7 1/2"
NORMAN	7 1/2"
QUEEN	9"
KING	9"
ESTATE	11 5/8"
CLOSURE	11 5/8"
UTILITY	11 5/8"




** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

4 Course Jack Arch

Table of Contents


Arch Gallery

ARC-02-1 Four Course Jack Arch One Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Four
D	Number of Pieces - One
E	Brick Size

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen.
The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




Height of Arch	4 COURSE
MODULAR	10 1/8"
NORMAN	10 1/8"
QUEEN	12 1/8"
KING	12 1/8"
ESTATE	15 5/8"
CLOSURE	15 5/8"
UTILITY	15 5/8"

4 Course Jack Arch

Table of Contents


Arch Gallery

ARC-02-2 Four Course Jack Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Four
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen.
Example "D" number of pieces shown is 2P.
The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

4 Course Jack Arch

Table of Contents


Arch Gallery

ARC-02-3 Four Course Jack Arch One Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Four
D	Number of Pieces - One
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen, as well as the dimensions of your chosen keystone. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




Height of Arch	4 COURSE
MODULAR	10 1/8"
NORMAN	10 1/8"
QUEEN	12 1/8"
KING	12 1/8"
ESTATE	15 5/8"
CLOSURE	15 5/8"
UTILITY	15 5/8"

4 Course Jack Arch

Table of Contents


Arch Gallery

ARC-02-4 Four Course Jack Arch Multi Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Four
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen, as well as the dimensions of your chosen keystone. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

5+ Course Jack Arch

Table of Contents


Arch Gallery

ARC-03-2 Five+ Course Jack Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Five+
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. Example "D" number of pieces shown is 2&3P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.



	5 COURSE	6 COURSE	7 COURSE
MODULAR	12 3/4"	15 3/8"	18"
NORMAN	12 3/4"	15 3/8"	18"
QUEEN	15 1/4"	18 3/8"	21 1/2"
KING	15 1/4"	18 3/8"	21 1/2"
ESTATE	19 5/8"	23 5/8"	27 5/8"
CLOSURE	19 5/8"	23 5/8"	27 5/8"
UTILITY	19 5/8"	23 5/8"	27 5/8"


Note: A five course arch from a single piece is not feasible, so there are no drawings for ARC-03-1 and ARC-03-3. Jack Arches over 5 courses require special attention. Your Acme representative will know to code it "CSS" when ordering for Custom Special Shape.

5+ Course Jack Arch

Table of Contents


Arch Gallery

ARC-03-4 Five+ Course Jack Arch Multi Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Jack Arch
B	Masonry Opening
C	Height of Arch in Courses - Five+
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen, as well as the dimensions of your chosen keystone. Example "D" number of pieces shown is 2&3P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Roman Arch

Table of Contents


Arch Gallery

ARC-04-1 Roman Arch One Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Roman
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size
I	Radius

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, radius, and brick size chosen. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Roman Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Roman Arch

Table of Contents


Arch Gallery

ARC-04-2 Roman Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Roman
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
I	Radius

Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, radius, and brick size chosen. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Roman Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Roman Arch

Table of Contents

Arch Gallery

ARC-04-3 Roman Arch One Piece with Keystone




For Roman Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Roman Arch

Table of Contents

Arch Gallery

ARC-04-4 Roman Arch Multi Piece with Keystone




For Roman Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Circular Arch

Table of Contents

Arch Gallery

ARC-05-1 Circular Arch One Piece




For Circular Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Circular Arch

Table of Contents

Arch Gallery

ARC-05-2 Circular Arch Multi Piece




For Circular Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Circular Arch

Table of Contents


Arch Gallery

ARC-05-3 Circular Arch One Piece with Keystones



ARCH DRAWING NOTATIONS	
A	Arch Type - Circular
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom
I	Radius

All joints to be a consistent 3/8."
Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, radius, and brick size chosen. As well as the dimensions of your keystone. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Circular Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Circular Arch

Table of Contents


Arch Gallery

ARC-05-4 Circular Arch Multi Piece with Keystones



ARCH DRAWING NOTATIONS	
A	Arch Type - Circular
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom
I	Radius

All joints to be a consistent 3/8."
Provide this arch number when ordering.
To draw your arch diagram we will need the width of the masonry opening, the height, radius, and brick size chosen. As well as the dimensions of your keystone. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Circular Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Segmental Arch

Table of Contents


Arch Gallery

ARC-06-1 Segmental Arch One Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Segmental
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size
I	Radius
J	Rise

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Segmental Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Segmental Arch

Table of Contents


Arch Gallery

ARC-06-2 Segmental Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Segmental
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
I	Radius
J	Rise

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Segmental Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Segmental Arch

Table of Contents


Arch Gallery

ARC-06-3 Segmental Arch One Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Segmental
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom
I	Radius
J	Rise

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. As well as the dimensions of your keystone. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Segmental Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Segmental Arch

Table of Contents


Arch Gallery

ARC-06-4 Segmental Arch Multi Piece with Keystone



ARCH DRAWING NOTATIONS	
A	Arch Type - Segmental
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom
I	Radius
J	Rise

Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. As well as the dimensions of your keystone. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Segmental Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Elliptical Arch

Table of Contents


Arch Gallery

ARC-07-1 Elliptical Arch One Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Elliptical
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size
I	Radius 1
J	Rise
K	Radius 2

All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Elliptical Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Elliptical Arch

Table of Contents


Arch Gallery

ARC-07-2 Elliptical Arch Multi Piece



ARCH DRAWING NOTATIONS	
A	Arch Type - Elliptical
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2P, 2PS, 2&3P, or 3PS)
E	Brick Size
I	Radius 1
J	Rise
K	Radius 2

All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, radius, rise, and brick size chosen. Example "D" number of pieces shown is 2P. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.




For Elliptical Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Elliptical Arch

Table of Contents

Arch Gallery

ARC-07-3 Elliptical Arch One Piece with Keystone




For Elliptical Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Elliptical Arch

Table of Contents

Arch Gallery

ARC-07-4 Elliptical Arch Multi Piece with Keystone




For Elliptical Arches, the arch pieces need to be tapered to maintain a consistent width mortar joint. If the pieces are not tapered, then the mortar joint will need to be tapered, which is less desirable. As the masonry opening gets larger, a field brick may be the best option, because the taper of the arch piece is less discernible. Send us your arch details and let us determine what is needed for the best application in these situations.

Jill Arch Keystones


Table of Contents

Arch Gallery


CAST KEY FLAT



CKF-05-1 Cast Key Flat, MOD/NOR




CKF-05-2 Cast Key Flat, KSZ/QSZ




CKF-05-3 Cast Key Flat, EST/CLS/UTL


5 Course



CKF-04-1 Cast Key Flat, MOD/NOR




CKF-04-2 Cast Key Flat, KSZ/QSZ




CKF-04-3 Cast Key Flat, EST/CLS/UTL


4 Course



CKF-03-1 Cast Key Flat, MOD/NOR




CKF-03-2 Cast Key Flat, KSZ/QSZ




CKF-03-3 Cast Key Flat, EST/CLS/UTL

3 Course


CAST KEY CHAMFERED



CKC-05-1 Cast Key Chamfered, MOD/NOR




CKC-05-2 Cast Key Chamfered, KSZ/QSZ




CKC-05-3 Cast Key Chamfered, EST/CLS/UTL


5 Course



CKC-04-1 Cast Key Chamfered, MOD/NOR




CKC-04-2 Cast Key Chamfered, KSZ/QSZ




CKC-04-3 Cast Key Chamfered, EST/CLS/UTL


4 Course



CKC-03-1 Cast Key Chamfered, MOD/NOR



CKC-03-2 Cast Key Chamfered, KSZ/QSZ



CKC-03-3 Cast Key Chamfered, EST/CLS/UTL


3 Course

Jill Arch Keystones


Table of Contents

Arch Gallery


CAST KEY RECESSED



CKR-05-1 Cast Key Recessed, MOD/NOR




CKR-05-2 Cast Key Recessed, KSZ/QSZ




CKR-05-3 Cast Key Recessed, EST/CLS/UTL


5 Course



CKR-04-1 Cast Key Recessed, MOD/NOR




CKR-04-2 Cast Key Recessed, KSZ/QSZ




CKR-04-3 Cast Key Recessed, EST/CLS/UTL


4 Course



CKR-03-1 Cast Key Recessed, MOD/NOR




CKR-03-2 Cast Key Recessed, KSZ/QSZ




CKR-03-3 Cast Key Recessed, EST/CLS/UTL

3 Course


BRICK KEY FLAT



BKF-05-1 Brick Key Flat, MOD/NOR




BKF-05-2 Brick Key Flat, KSZ/QSZ




BKF-05-3 Brick Key Flat, EST/CLS/UTL


5 Course



BKF-04-1 Brick Key Flat, MOD/NOR




BKF-04-2 Brick Key Flat, KSZ/QSZ




BKF-04-3 Brick Key Flat, EST/CLS/UTL


4 Course



BKF-03-1 Brick Key Flat, MOD/NOR



BKF-03-2 Brick Key Flat, KSZ/QSZ



BKF-03-3 Brick Key Flat, EST/CLS/UTL

3 Course


Jill Arch

Table of Contents

Arch Gallery

ARC-08 Jill Arch Keystone Dimensions

Keystones for Jill arches are required to have an angle of 74.8°. All keys utilize the same overall dimensions regardless of face detail. Ask your representative to order Cast Stone Keystones. Flat, Chamfered and Recessed faces are available. Please note, that even though these are labelled as Jill Arch keystones, these can also be used with custom Jack Arches as well.



JILL ARCH KEYSTONE DIMENSIONS							
CODE	# OF COURSES	SIZE	F Height	G Top	H Bottom	Depth	Angle
CKF-03-1 CKC-03-1 CKR-03-1 BKF-03-1	3 Course	MODULAR / NORMAN	7 1/2"	7 13/16"	3 3/4"	3 5/8"	74.8°
CKF-04-1 CKC-04-1 CKR-04-1 BKF-04-1	4 Course	MODULAR / NORMAN	10 1/8"	9 1/4"	3 3/4"	3 5/8"	74.8°
CKF-05-1 CKC-05-1 CKR-05-1 BKF-05-1	5 Course	MODULAR / NORMAN	1' 3/4"	10 11/26"	3 3/4"	3 5/8"	74.8°
CKF-03-2 CKC-03-2 CKR-03-2 BKF-03-2	3 Course	QUEEN/ KING	9"	8 5/8"	3 3/4"	3"	74.8°
CKF-04-2 CKC-04-2 CKR-04-2 BKF-04-2	4 Course	QUEEN/ KING	1' 1/8"	10 11/32"	3 3/4"	3"	74.8°
CKF-05-2 CKC-05-2 CKR-05-2 BKF-05-2	5 Course	QUEEN/ KING	1' 3 1/4"	1' 1/32"	3 3/4"	3"	74.8°
CKF-03-3 CKC-03-3 CKR-03-3 BKF-03-3	3 Course	ESTATE / CLOSURE/ UTILITY	11 5/8"	10 1/16"	3 3/4"	3 5/8"	74.8°
CKF-04-3 CKC-04-3 CKR-04-3 BKF-04-3	4 Course	ESTATE / CLOSURE/ UTILITY	1' 3 5/8"	1' 1/4"	3 3/4"	3 5/8"	74.8°
CKF-05-3 CKC-05-3 CKR-05-3 BKF-05-3	5 Course	ESTATE / CLOSURE/ UTILITY	1' 7 5/8"	1' 2 13/32"	3 3/4"	3 5/8"	74.8°

Jill Arch

Table of Contents

Arch Gallery

ARC-08 Jack Arch vs Jill Arch Diagram


Jill Arches require a righthand and lefthand piece for either side of the keystone to ensure that any colors, textures, or coatings match the surrounding wall of face brick. Arches up to 5 courses tall can be created from slanted pieces which correspond to the size of the face brick. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.

Jack Arch

ARC-01-3, ARC-02-3

Jill Arch

ARC-08-3




Jill Arch - MOD/NOR


Table of Contents

Arch Gallery

ARC-08-3 Jill Arch One Piece with Keystone - Modular & Norman Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size - Modular/Norman
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.


The plant will produce both a left "L1" and right "R1" pieces with finished faces on the stretcher and top and bottom header sides to match the field brick.




Three Course Keystone with Three Course One Piece Jill Arch - MOD/NOR



Four Course Keystone with Four Course One Piece Jill Arch - MOD/NOR



Four Course Keystone with Three Course One Piece Jill Arch - MOD/NOR



Five Course Keystone with Four Course One Piece Jill Arch - MOD/NOR


Note: A Jill arch is specifically designed to work around a keystone, therefore there are no drawings for ARC-08-1 and ARC-08-2. See page 158 for the specific dimensions based on brick size.

Jill Arch - MOD/NOR


Table of Contents

Arch Gallery

ARC-08-4 Jill Arch Multi Piece with Keystone - Modular & Norman Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2PS, 3PS)
E	Brick Size - Modular/Norman
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. Example "D" number of pieces shown is 2PS. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.


Multi Piece Jill Arches use the same single pieces "R1" and "L1" as produced for One Piece Jill Arches. **Multi Piece Jill Arches require "R1 and L1" to be *Field Cut on site to create A and B pieces.**




Three Course Keystone with Three Course Multi Piece Jill Arch - MOD/NOR




Four Course Keystone with Four Course Multi Piece Jill Arch - MOD/NOR



Four Course Keystone with Three Course Multi Piece Jill Arch - MOD/NOR



Five Course Keystone with Four Course Multi Piece Jill Arch - MOD/NOR



Five Course Keystone with Five Course Multi Piece Jill Arch - MOD/NOR


** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Jill Arch - KSZ/QSZ


Table of Contents

Arch Gallery

ARC-08-3 Jill Arch One Piece with Keystone - King & Queen Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size - King/Queen
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.

The plant will produce both a left "L1" and right "R1" pieces with finished faces on the stretcher and top and bottom header sides to match the field brick.



Three Course Keystone with Three Course One Piece Jill Arch - KSZ/QSZ



Four Course Keystone with Three Course One Piece Jill Arch - KSZ/QSZ


Note: A Jill arch is specifically designed to work around a keystone, therefore there are no drawings for ARC-08-1 and ARC-08-2. See page 158 for the specific dimensions based on brick size.

Jill Arch - KSZ/QSZ


Table of Contents

Arch Gallery

ARC-08-4 Jill Arch Multi Piece with Keystone - King & Queen Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2PS, 3PS)
E	Brick Size - King/Queen
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. Example "D" number of pieces shown is 2PS. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.


Multi Piece Jill Arches use the same single pieces "R1 and L1" as produced for One Piece Jill Arches. **Multi Piece Jill Arches require "R1 and L1" to be *Field Cut on site to create A and B pieces.**




Three Course Keystone with Three Course Multi Piece Jill Arch - KSZ/QSZ




Four Course Keystone with Four Course Multi Piece Jill Arch - KSZ/QSZ



Four Course Keystone with Three Course Multi Piece Jill Arch - KSZ/QSZ



Five Course Keystone with Four Course Multi Piece Jill Arch - KSZ/QSZ



Five Course Keystone with Five Course Multi Piece Jill Arch - KSZ/QSZ


** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.

Jill Arch - EST/CLO/UTL


Table of Contents

Arch Gallery

ARC-08-3 Jill Arch One Piece with Keystone - Estate, Closure & Utility Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - One
E	Brick Size - Estate/Closure/Utility
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. The field brick size determines the bed depth of the Arch Pieces and they are typically cored. Cores are typically 1/2" back from the finished face.

The plant will produce both a left "L1" and right "R1" pieces with finished faces on the stretcher and top and bottom header sides to match the field brick.



Three Course Keystone with Three Course One Piece Jill Arch - EST/CLO/UTL



Four Course Keystone with Three Course One Piece Jill Arch - EST/CLO/UTL


Note: A Jill arch is specifically designed to work around a keystone, therefore there are no drawings for ARC-08-1 and ARC-08-2. See page 158 for the specific dimensions based on brick size.

Jill Arch - EST/CLO/UTL


Table of Contents

Arch Gallery

ARC-08-4 Jill Arch Multi Piece with Keystone - Estate, Closure & Utility Sizes




ARCH DRAWING NOTATIONS	
A	Arch Type - Jill
B	Masonry Opening
C	Height of Arch in inches
D	Number of Pieces - (2PS, 3PS)
E	Brick Size - Estate/Closure/Utility
F	Key Height - in inches or courses
G	Key Top
H	Key Bottom




All joints to be a consistent 3/8." Provide this arch number when ordering. To draw your arch diagram we will need the width of the masonry opening, the height, and brick size chosen. A keystone is required to create this arch. Example "D" number of pieces shown is 2PS. The field brick size determines the bed depth of the Arch Pieces and they are typically cored.


Multi Piece Jill Arches use the same single pieces "R1 and L1" as produced for One Piece Jill Arches. **Multi Piece Jill Arches require "R1 and L1" to be *Field Cut on site to create A, B and C pieces.**




Three Course Keystone with Three Course Multi Piece Jill Arch - EST/CLO/UTL




Four Course Keystone with Four Course Multi Piece Jill Arch - EST/CLO/UTL



Four Course Keystone with Three Course Multi Piece Jill Arch - EST/CLO/UTL



Five Course Keystone with Four Course Multi Piece Jill Arch - EST/CLO/UTL



Five Course Keystone with Five Course Multi Piece Jill Arch - EST/CLO/UTL

** Please note: Not all shapes can be made at every location. Check with your sales representative before making selections.


Reading Shape Documentation

Once you are ready to order shapes, it is time for the plants, architects and our engineering department to communicate clearly what each shape looks like and functions as. Included in the approval drawings is a "Letter of Transmittal."


This document has a list of ALL shapes needed to complete a job. An example here is laid out for you.

Each shape may have:


An approval drawing (#)



An in wall use drawing (#u)



A green brick drawing (#g)



After these are approved by the customer, they are sent to the plant for manufacturing.

Sales person requesting shape approval drawing. Required for customer approval.

Job Information

Revision Letter, from A to Z, changes with each revision to the drawing.

List of all shapes for a job. In this example there are 4 shapes.

There are six documents. An approval drawing for shapes 1, 2, 3 & 4.

A usage drawing (3u) for 1, 2, and 3 together, as they are related shapes, and a separate usage drawing (4u) for shape 4.

Status Codes denote if this document requires approval or if it is simply fyi.

Indicates your shape engineer.

Other associates who will receive this document.

LETTER OF TRANSMITTAL

DATE 2/14/2023

TO: JASON HAMILTON
294-DFW

CUSTOMER:
GFF
JOB NAME:
LEFT BANK
JOB LOCATION:
FORT WORTH, TX

REMARKS HERE ARE THE SHOP DRAWINGS YOU REQUESTED.

REVISION A - CHANGED BLEND AND ADDED QUANTITY.

NOTE :

DWG. NO.	SHEET / SHAPE	REV.	PLANT	SHAPE DESCRIPTION	QTY.	ASSOCIATED DRAWINGS
200A1468	1	A	DTP	SHA-01-1 Shelf Angle Stretcher	.75x.5	9500
200A1468	2	A	DTP	SHA-01-2 Shelf Angle Stretcher Corner Left	.75x.5	25
200A1468	3	A	DTP	SHA-01-3 Shelf Angle Stretcher Corner Right	.75x.5	25
200A1468	3u	A	DTP	SHA-01-1 Shelf Angle Stretcher & Corners	Usage	
200A1468	4	A	DTP	CNR-01-2 Corner External Long	165°	225
200A1468	4u	A	DTP	CNR-01-2 Corner External Long	Usage	

COPY TO:
JIM OGG/CORY BARRON
MARK BURDEN
TOM JETER

LOCATION	CODE
DTP	1
DFW	2
NTR	2
----	2
----	2

STATUS CODES:
1 For approval 2 For your information

By: TDG
Acme Brick Co. - FWGO
TDG - Todd Goodson




Table of Contents

Reading Shape Documentation

Here are examples of an approval drawing (#), a usage drawing (#u), and a green brick drawing (#g) which shows the before firing size accounting for shrinkage. Information across the bottom of the drawings will be common to all drawings. Information needed is as follows (with examples).

- Customer: *Architect, Contractor or Mason Name*
- Job Name: *Brownsville International Airport*
- Job Location: *Brownsville, Tx*
- Plant to Manufacture: *PEP (Perla Eastgate Plant)*
- Blend (Number, Name, Texture, Size): *PEP167 Slate Gray, Velour, Utility Size*
- Cored or Solid: *Cored*
- Usage Drawing, Finished Faces (FF): *Provide an architectural drawing, in pdf format, showing the shapes in use.*
- Quantity: *1500*

Approval Drawing (shape number)



Customer approval signature

Shape information: brick plant, color, size and quantity.

BE (brick equivalent) number


Revision letter and date of revision

Revision Letter

Job Information

Date of original drawing


Usage Drawing (shape number + "u")



Usage diagram can be provided by either the architect or Acme's engineering department.

Note the 3u shape drawing designation - "u" for usage

Green Drawing (shape number + "g")



Green size (before) and Fired size (after) calculated to ensure finished in wall dimensions are correct.

Notes

[illegible][illegible]



Acme Brick Company
(817) 332-4101
3024 Acme Brick Plaza
Fort Worth, TX 76109



See it all come together
in stunning design.

